

draft

GENERAL PROJECT INFORMATION

Brecksville-Broadview Heights CSD Project Name

Elementary School & Field House Project Type: K-3, K-12, High School, etc.

Brecksville, OH Project City, State

DD Est. Type: Schematic Design, Design Dev, Construction

5/19/2019 (updated 6/3/19) Date of Estimate

Jenny Naas
Senior Estimator

6860 W. Snowville Road, Suite 100
Brecksville, OH 44141
800-705-5251
jnaas@shookconstruction.com



Brecksville-Broadview Heights CSD

Brecksville, OH

Est. Type:

DD

Date:

5/19/2019

(updated 6/3/19)

Gross Area (gsf) Tabulation

Description of Areas	Total New Areas	Total Renovations	Total GSF New+Renov
First Floor			
Conventional School Bldg Construction	89,713		89,713
PEMB Field House Construction	32,159		32,159
Second Floor	54,642		54,642
Total Gross Square Footage	176,514	-	176,514

Brecksville-Broadview Heights CSD

Brecksville, OH

Est. Type:

DD

Date:

5/19/2019

(updated

6/3/19)

Elementary School & Field House**Clarifications****DD Clarifications**

1	This estimate is based on drawings, specs, and narratives received on 4-19-19 and 4-24-19 as well as conversations and email exchanges with the design team and as clarified below.
2	Project is figured as sales tax-exempt.
3	No soft costs, tap fees, or aid to construction are included in the estimate. These would be owner costs.
4	The estimated value reflects a balanced site - no haul off; no import.
5	Aside from elements incorporated into the current design, no cost has been included for wetlands remediation.
6	No costs for wetland credits, etc. are included in the estimate. Note: approximately 11.75 acres of mosaic wetlands and 1.28 acres of category 2 wetlands disturbed.
7	Monies have been included for cement stabilization at the building pad to create an adequate working surface for the winter earthwork schedule. Monies have also been included for a single lift of lime stabilization at the paved areas to accommodate winter construction. A \$135,000 allowance has been included for additional drying techniques.
8	To eliminate waiting time for concrete floors or asphalt pavement placement dictated in the soil report during cool and wet excavations, ODOT No. 304 crushed aggregate has been estimated in fill areas greater than 4'.
9	A \$500,000 allowance has been included towards any Oakes Road traffic improvements/widening. No other improvements along Oakes Road or Valley Parkway have been included in the estimate.
10	Unless it can be covered within the allowance listed above, no traffic light has been included in the estimate.
11	PK playground soft surface is estimated as a Poured in Place Safety Playground Surface.
12	Elementary playground soft surface is estimated as a Mulch Area.
13	A \$100,000 Allowance is included for New PK & Relocated Elementary Playground Equipment.
14	A MRVA 900 admixture in the concrete is included for moisture mitigation at the floors.
15	A \$100,000 allowance is included in the estimate for any Additional Special Ceiling Finishes/Clouds.
16	A \$100,000 allowance is included in the estimate for any Additional Interior Design Wall Features.
17	Acoustical Wall Panels are included as shown in student dining and the small music rooms. In addition, allowances of \$15,000 for the large music room, \$15,000 for other school areas, and \$80,000 at the fieldhouse have been included in the estimate.
18	A \$150,00 allowance has been included in the estimate for purchase of a Primary Transformer.
19	No premiums have been included in the estimate for custom colors. Materials should be selected from manufacturers listing of standard color selections.
20	Metal building specifications issued as part of the DD submittal will be modified to fit the estimate. Project will specify metal building manufacturer insulated wall panels (3"). Wall panels on the exterior to all be same style, width, and single standard color.
21	Estimate carries a \$40,000 allowance for lighting at the raised platform. There is no stage lighting included in the estimate.
22	Aid to construction/power company charges are figured to be by owner and are not included in the estimate.
23	Current estimate does not include premium time to account for a potential expedited schedule.

Brecksville-Broadview Heights CSD
Brecksville, OH

New G.S.F.: 176,514 SF
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

Elementary School & Field House

Element Description	Cost	Cost/SF	Fieldhouse	School
Subcontractor GC's	\$315,960	\$1.79	\$57,565	\$258,395
Subcontractor Bonding	\$446,482	\$2.53	\$79,604	\$366,878
Foundations	\$1,023,912	\$5.80	\$238,314	\$785,598
Substructure	\$1,282,013	\$7.26	\$264,426	\$1,017,587
Superstructure	\$4,018,133	\$22.76	\$1,322,630	\$2,695,503
Fabrications	\$204,029	\$1.16	\$2,250	\$201,779
Exterior Closure	\$3,468,851	\$19.65	\$203,761	\$3,265,090
Exterior Windows & Doors	\$1,669,984	\$9.46	\$125,664	\$1,544,320
Roof	\$2,251,787	\$12.76	\$5,100	\$2,246,687
Interior Partitions	\$2,143,800	\$12.15	\$108,550	\$2,035,250
Interior Windows & Doors	\$944,163	\$5.35	\$26,731	\$917,432
Interior Finishes	\$2,941,537	\$16.66	\$416,777	\$2,524,760
Specialties/Fittings	\$472,416	\$2.68	\$27,940	\$444,476
Food Service	\$780,000	\$4.42	\$0	\$780,000
Casework	\$1,168,200	\$6.62	\$6,960	\$1,161,240
Athletics	\$300,372	\$1.70	\$300,372	\$0
Theatrical	\$35,500	\$0.20	\$0	\$35,500
Equipment	\$28,850	\$0.16	\$0	\$28,850
Conveying	\$215,000	\$1.22	\$0	\$215,000
Plumbing	\$2,901,500	\$16.44	\$65,750	\$2,835,750
Fire Protection	\$485,414	\$2.75	\$88,437	\$396,976
HVAC	\$4,558,000	\$25.82	\$393,500	\$4,164,500
Electrical	\$4,812,217	\$27.26	\$695,000	\$4,117,217
Technology & Cabling	\$1,724,000	\$9.77	\$223,000	\$1,501,000
Site Demolition	\$149,450	\$0.85	\$74,725	\$74,725
Site Preparation	\$1,672,238	\$9.47	\$836,119	\$836,119
Site Pavings	\$2,410,524	\$13.66	\$1,205,262	\$1,205,262
Site Improvements	\$498,806	\$2.83	\$3,800	\$495,006
Site Landscape	\$252,059	\$1.43	\$126,030	\$126,030
Site Water	\$356,016	\$2.02	\$178,008	\$178,008
Site Gas	\$0	\$0.00	\$0	\$0
Site Sanitary	\$102,564	\$0.58	\$51,282	\$51,282
Site Storm	\$472,184	\$2.68	\$236,092	\$236,092
Subtotal - Building	\$38,192,119	\$216.37	\$4,652,330	\$33,539,788
Subtotal - Site	\$5,913,842	\$33.50	\$2,711,318	\$3,202,524
Subtotal - Building plus Site	\$44,105,960	\$249.87	\$7,363,648	\$36,742,312
Loose Furnishings/ FFE	\$ 1,692,627	\$9.59	\$25,000.00	\$1,667,627.00
Subtotal - Building; Site; FFE	\$ 45,798,587	\$259.46	\$ 7,388,648	\$ 38,409,939
Estimate Contingency (3.5%)	\$ 1,602,951	\$9.08	\$ 258,603	\$ 1,344,348
Subtotal - Building; Site; FFE; Estimate Contingency	\$ 47,401,538	\$268.54	\$ 7,647,251	\$ 39,754,287
Total - Estimated Cost	\$ 47,401,538	\$268.54	\$ 7,647,251	\$ 39,754,287
Project Budget	\$ 40,589,307		\$7,236,769	\$33,352,538
Budget Difference - (over) / under	\$ (6,812,231)		\$ (410,482)	\$ (6,401,749)

SD HARD COST BUDGETS:

Elem School: \$1,779,459.67 site
\$30,250,814.31 building
\$1,779,459.67 furnishings
\$1,779,459.67 tech
\$35,589,193.30 Design Budget

Field House: \$1,834,425.00 site
\$5,352,343.76 building
\$25,000.00 furnishings
\$25,000.00 tech
\$7,236,768.76 Design Budget

Total Budget: \$42,825,962

DD HARD COST BUDGETS:

Elem School: \$1,667,627.00 site
\$28,349,657.00 building
\$1,667,627.00 furnishings
\$1,667,627.00 tech
\$33,352,538.00 Design Budget

Field House: \$1,834,425.00 site
\$5,352,343.76 building
\$25,000.00 furnishings
\$25,000.00 tech
\$7,236,768.76 Design Budget

Total Budget: \$40,589,307



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

	Qty	Unit	Base Unit Cost	Adjusted Unit Cost	SubTtl
Subcontractor GC's					
School Sub's General Requirements (M,E,P,FP,Tech not included)	144,355	Sf	\$1.79	\$1.79	\$258,395
F Field House Sub's General Requirements (M,E,P,FP,Tech not incl)	32,159	Sf	\$1.79	\$1.79	\$57,565
					\$315,960
Subcontractor Bonding					
Bonding - school	1.1	%	\$333,525	\$333,525	\$366,878
F Bonding - fieldhouse	1.1	%	\$72,368	\$72,368	\$79,604
					\$446,482
Foundations					
Concrete Footing Perimeter - school	544	Cy	\$415.00	\$415.00	\$225,939
F Concrete Footing Perimeter - fieldhouse	174	Cy	\$415.00	\$415.00	\$72,318
Concrete Blankets - winter work	1	Ls	\$26,250.00	\$26,250.00	\$26,250
F Concrete Blankets - winter work	1	Ls	\$8,750.00	\$8,750.00	\$8,750
16" Fnd System: 8"CMU+4"Cavity+4"FaceCMU w/ Resteel - school	3,386	Sf	\$29.61	\$29.61	\$100,265
Allow for lower foundation level at NW corner based on PSI note: All the building foundation should be extend to the natural soils. 16" Fnd System: 8"CMU+4"Cavity+4"FaceCMU w/ Resteel - school	730	Sf	\$29.61	\$29.61	\$21,615
F 16" Fnd System: 8"CMU+4"Cavity+4"FaceCMU w/ Resteel - fieldhouse	1,120	Sf	\$29.61	\$29.61	\$33,170
Concrete Footing Interior Wall - school	212	Cy	\$405.00	\$405.00	\$85,959
F Concrete Footing Interior Wall - fieldhouse	16	Cy	\$405.00	\$405.00	\$6,552
F Concrete Tie Beams - fieldhouse	107	Cy	\$405.00	\$405.00	\$43,275
CMU Foundation Wall Interior (8") - school	2,038	Sf	\$15.80	\$15.80	\$32,203
F CMU Foundation Wall Interior (8") - fieldhouse	279	Sf	\$15.80	\$15.80	\$4,404
Spread Ftgs. Column Type - school	343	Cy	\$395.00	\$395.00	\$135,557
F Spread Ftgs. Column Type - fieldhouse	97	Cy	\$395.00	\$395.00	\$38,389
Concrete Pier/Pilaster - school	74	Cy	\$1,000.00	\$1,000.00	\$73,981
F Concrete Pier/Pilaster - fieldhouse	17	Cy	\$1,000.00	\$1,000.00	\$16,873
Exterior Stoops - school	36	Cy	\$700.00	\$700.00	\$25,049
F Exterior Stoops - fieldhouse	12	Cy	\$700.00	\$700.00	\$8,401
Set Anchor Bolts And Grout Base Plates - school	159	Sets	\$237.75	\$237.75	\$37,802
F Set Anchor Bolts And Grout Base Plates - fieldhouse	26	Sets	\$237.75	\$237.75	\$6,182
Temporary Dewatering	1	Allw	\$5,000.00	\$5,000.00	\$5,000
Flowable Fill Concrete	100	Cy	\$100.00	\$100.00	\$10,000
Waterproofing (below Grade)	1,220	Sf	\$4.90	\$4.90	\$5,978
					\$1,023,912
Substructure					
4" Concrete Slab On Grade - school	89,713	Sf	\$5.52	\$5.52	\$495,216
F 5" Concrete Slab On Grade - fieldhouse	32,159	Sf	\$5.83	\$5.83	\$187,487
F upcharge for #4 rebar in lieu of W.W.F. - fieldhouse	32,159	Sf	\$0.65	\$0.65	\$20,903
Redress Top 2" Base Granular Fill Below Slab (6") - school	89,713	Sf	\$0.31	\$0.31	\$27,689
F Redress Top 2" Base Granular Fill Below Slab (6") - fieldhouse	32,159	Sf	\$0.31	\$0.31	\$9,926
Thickened Slab @ Interior Walls	218	Lf	\$7.50	\$7.50	\$1,635
Thickened Slab @ Column Ftg / Column Boxout - school	159	Ea	\$150.00	\$150.00	\$23,850
F Thickened Slab @ Column Ftg / Column Boxout - fieldhouse	26	Ea	\$150.00	\$150.00	\$3,900



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: DD
Date: Date: 5/19/2019 (updated 6/3/19)

	MRVA 900 Admixture (eliminates need for moisture mitigation in flooring spec) @ Slab - school	1,120 Cy	\$55.00	\$55.00	\$61,610
F	MRVA 900 Admixture (eliminates need for moisture mitigation in flooring spec) @ Slab - fieldhouse	496 Cy	\$55.00	\$55.00	\$27,295
	10 Mil Vapor Barrier Under Slab On Grade - school	89,713 Sf	\$0.30	\$0.30	\$26,914
F	10 Mil Vapor Barrier Under Slab On Grade - fieldhouse	32,159 Sf	\$0.30	\$0.30	\$9,648
	Perimeter Insulation @ Foundation - school	7,581 Sf	\$2.10	\$2.10	\$15,920
F	Perimeter Insulation @ Foundation - fieldhouse	2,508 Sf	\$2.10	\$2.10	\$5,267
	Concrete Stair Sets (5 risers)	1 Set	\$2,750.00	\$2,750.00	\$2,750
	Concrete Stair - Stage	83 Lfr	\$75.00	\$75.00	\$6,225
	Concrete Stair - Feature Stair (F)	360 Lfr	\$75.00	\$75.00	\$27,000
	Concrete Stair Landing - Feature Stair (F)	156 Sf	\$10.00	\$10.00	\$1,560
	Concrete Ramp	155 Sf	\$7.00	\$7.00	\$1,085
	3.5" Concrete On Metal Deck - 2nd fl (Deck Not Incl)	54,642 Sf	\$5.40	\$5.40	\$295,067
	Cooler/Freezer Pad (insulated double slab)	368 Sf	\$12.00	\$12.00	\$4,416
	Elevator Pit	2 Ea	\$4,950.00	\$4,950.00	\$9,900
	Concrete Fill at Metal Pan Stair (floor to floor)	6 Ea	\$1,500.00	\$1,500.00	\$9,000
	Embedded Iron Allowance	1 Ls	\$5,250.00	\$5,250.00	\$5,250
	Additional Rebar Allowance	1 Tn	\$2,500.00	\$2,500.00	\$2,500
					\$1,282,013

Superstructure

F	PEMB - fieldhouse (insulated metal panels 26 ga. w/ ribbed profile (ThermaClad Shallow Plank)	32,159 Sf	\$40.00	\$40.00	\$1,286,360
	Structural Steel Beams	265 Tn	\$3,875.00	\$3,875.00	\$1,025,856
	Structural Steel Columns	76 Tn	\$3,875.00	\$3,875.00	\$295,113
	Steel Joists K Series	55 Tn	\$3,875.00	\$3,875.00	\$214,769
	Steel Joists KCS Series	6 Tn	\$3,875.00	\$3,875.00	\$23,948
	Steel to accommodate Canopy Design	6 Tn	\$3,875.00	\$3,875.00	\$23,793
F	Steel to accommodate Gym Divider Curtains (3)	6 Tn	\$3,875.00	\$3,875.00	\$22,669
F	Steel to accommodate Basketball Backstops (12)	3.51 Tn	\$3,875.00	\$3,875.00	\$13,601
	Additional Steel Allowance	3 Tn	\$3,875.00	\$3,875.00	\$11,625
	Bridging	18.9 Tn	\$3,875.00	\$3,875.00	\$73,412
	Masonry Support Steel	35.8 Tn	\$3,875.00	\$3,875.00	\$138,667
	Miscellaneous Structural Framing	18,945 Lbs	\$2.50	\$2.50	\$47,362
	Bearing Plates, L Angles, C Channels	23,155 Lbs	\$2.50	\$2.50	\$57,887
	Additional Miscellaneous Metals Allowance	2 Tn	\$5,000.00	\$5,000.00	\$10,000
	Moment Connections	164 Ea	\$275.00	\$275.00	\$45,100
	Shear Studs	6,521 Ea	\$3.00	\$3.00	\$19,563
	Light Gage CFS Trusses (Type 1,2,3,4)	1 Ls	\$183,710.00	\$183,710.00	\$183,710
	Metal Floor Deck (3" x 20 Ga Composite)	54,642 Sf	\$4.25	\$4.25	\$232,229
	Metal Roof Deck (1 1/2" x 22 Ga.)	97,490 Sf	\$3.00	\$3.00	\$292,470
					\$4,018,133

Fabrications

	Ladders (roof ladder)	2 Ea	\$1,500.00	\$1,500.00	\$3,000
	Ladders - Ship(Cage) Type	3 Ea	\$2,250.00	\$2,250.00	\$6,750
F	Ladders - Ship(Cage) Type - fieldhouse	1 Ea	\$2,250.00	\$2,250.00	\$2,250
	Metal Pan Stair Set (floor to floor)	6 Ea	\$15,000.00	\$15,000.00	\$90,000
	Metal Pan Landing	215 Sf	\$75.00	\$75.00	\$16,125
	Railing (Full Rake) - Steel w/ horiz pickets	37 Lf	\$258.50	\$258.50	\$9,565
	Wall Mounted Assist Railings (Steel)	353 Lf	\$60.50	\$60.50	\$21,357
	Assist Railings @ Full Rake (Steel)	37 Lf	\$27.50	\$27.50	\$1,018
	Railing (Full Level) - Aluminum Ornamental w/Glass	71 Lf	\$445.50	\$445.50	\$31,631



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: DD
Date: Date: 5/19/2019 (updated 6/3/19)

Railing (Full Rake)- Aluminum Ornamental w/Glass	30 Lf	\$500.50	\$500.50	\$15,015
Assist Railings @ Full Rake (Aluminum)	30 Lf	\$44.00	\$44.00	\$1,320
Steel Bollards	8 Ea	\$750.00	\$750.00	\$6,000
				\$204,029

Exterior Closure

Wall X1 on A500 (typ brick on masonry - 8" CMU):

8" Block Backup + Resteel	3,886 Sf	\$15.75	\$15.75	\$61,209
Fluid-applied vapor-permeable Air/Water Barrier ABBA	3,886 Sf	\$4.00	\$4.00	\$15,545
3" Rigid Insulation	3,886 Sf	\$2.90	\$2.90	\$11,270
Face Brick Veneer - 3-5/8 inches by 3-5/8 inches by 11-5/8 inches (utility brick)	3,886 Sf	\$22.75	\$22.75	\$88,413

Wall X2 on A500 (typ brick on stud wall):

Stud wall assembly: Interior type X drywall; 6" metal stud framing; R21 batt insul; exterior type X drywall; fluid applied air & water barrier (ABBA); 1 1/2" rigid insulation	27,550 Sf	\$23.56	\$23.56	\$649,081
Face Brick Veneer - 3-5/8 inches by 3-5/8 inches by 11-5/8 inches (utility brick)	27,550 Sf	\$22.75	\$22.75	\$626,766

Wall X2a/X5/X9 (typ split faced CMU or stone on stud wall):

Stud wall assembly: Interior type X drywall; 6" metal stud framing; R21 batt insul; exterior type X drywall; fluid applied air & water barrier (ABBA); 1 1/2" rigid insulation	2,168 Sf	\$23.56	\$23.56	\$51,069
CMU Veneer - (split faced)	1,792 Sf	\$18.15	\$18.15	\$32,518
Premium for pattern at split faced CMU	1,577 Sf	\$10.00	\$10.00	\$15,766
Stone Veneer	376 Sf	\$50.00	\$50.00	\$18,800

Wall X3 on A500 (typ fiber cement panel on stud wall):

Stud wall assembly: Interior type X drywall; 6" metal stud framing; R21 batt insul; exterior type X drywall; fluid applied air & water barrier (ABBA); 1 1/2" rigid insulation	20,597 Sf	\$23.56	\$23.56	\$485,266
1 1/2" CFMF hat channel	20,597 Sf	\$1.52	\$1.52	\$31,307
Fiber Cement Panel	20,597 Sf	\$31.95	\$31.95	\$658,075

Wall ?? (typ non-insulated metal panel on stud wall):

Stud wall assembly: Interior type X drywall; 6" metal stud framing; R21 batt insul; exterior type X drywall; fluid applied air & water barrier (ABBA); 1 1/2" rigid insulation	Sf	\$23.56	\$23.56	\$0
1 1/2" CFMF hat channel	Sf	\$1.52	\$1.52	\$0
Centria Concealed Fastener Metal Panel (non-insulated)	Sf	\$28.79	\$28.79	\$0

Wall X3a/X10 (typ fiber cement panel on masonry - 8" CMU):

8" Block Backup + Resteel	1,542 Sf	\$15.75	\$15.75	\$24,289
Fluid-applied vapor-permeable Air/Water Barrier ABBA	1,542 Sf	\$4.00	\$4.00	\$6,169
3" Rigid Insulation	1,542 Sf	\$2.90	\$2.90	\$4,472
1 1/2" CFMF hat channel	1,542 Sf	\$1.52	\$1.52	\$2,344
Fiber Cement Panel	1,542 Sf	\$31.95	\$31.95	\$49,272

Wall X4 on A500 (typ split faced CMU on masonry - 8" CMU):

8" Block Backup + Resteel	2,007 Sf	\$15.75	\$15.75	\$31,604
Fluid-applied vapor-permeable Air/Water Barrier ABBA	2,007 Sf	\$4.00	\$4.00	\$8,026
3" Rigid Insulation	2,007 Sf	\$2.90	\$2.90	\$5,819
CMU Veneer - (split faced)	2,007 Sf	\$18.15	\$18.15	\$36,420
Premium for pattern at split faced CMU	1,405 Sf	\$10.00	\$10.00	\$14,046

F Fieldhouse Wall X1 on A500 (typ brick on masonry - 8" CMU):

F 8" Block Backup + Resteel	1,254 Sf	\$15.75	\$15.75	\$19,751
F Fluid-applied vapor-permeable Air/Water Barrier ABBA	1,254 Sf	\$4.00	\$4.00	\$5,016
F 3" Rigid Insulation	1,254 Sf	\$2.90	\$2.90	\$3,637
F Face Brick Veneer - 3-5/8 inches by 3-5/8 inches by 11-5/8 inches (utility brick)	1,254 Sf	\$22.75	\$22.75	\$28,529



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

F	CMU Veneer - (split face)	192 Sf	\$18.15	\$18.15	\$3,485
F	<u>Fieldhouse Wall X1* on A500 (typ brick on masonry - 12" CMU*):</u>				
F	12" Block Backup + Resteel	96 Sf	\$18.75	\$18.75	\$1,800
F	Fluid-applied vapor-permeable Air/Water Barrier ABBA	96 Sf	\$4.00	\$4.00	\$384
F	3" Rigid Insulation	96 Sf	\$2.90	\$2.90	\$278
F	Face Brick Veneer - 3-5/8 inches by 3-5/8 inches by 11-5/8 inches (utility brick)	96 Sf	\$22.75	\$22.75	\$2,184
F	<u>Fieldhouse Wall X6 on A500 (typ brick on masonry - 12" CMU*):</u>				
F	12" Block Backup + Resteel	4,524 Sf	\$18.75	\$18.75	\$84,825
F	1.5" CFMF Hat Channel (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	Insulated Metal Panel System (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	<u>Fieldhouse Wall X7 on A500 (typ brick on masonry - 8" CMU):</u>				
F	8" Block Backup + Resteel	2,930 Sf	\$15.75	\$15.75	\$46,155
F	7/8" CFMF Hat Channel (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	Insulated Metal Panel System (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	<u>Fieldhouse Wall X8 on A500 (insulated metal panel on z-girts):</u>				
F	Z-Girts (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	PEMB Interior Surface (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
F	Insulated Metal Panel System (w/ PEMB scope)	0 Sf	\$0.00	\$0.00	\$0
	Premium for labor at curved walls	494 Sf	\$50.00	\$50.00	\$24,700
	Labor Premium at Hexagon Window	23 Ea	\$1,000.00	\$1,000.00	\$23,000
	Soffit - Framed Assembly w/Fiber Cement Panel	688 Sf	\$54.22	\$54.22	\$37,308
	stud extention at soffit (B7)	1,204 Sf	\$6.64	\$6.64	\$7,995
	Soffit - >1' deep Fiber Cement Soffit @ Roof Perimeter	2,370 Lf	\$54.22	\$54.22	\$128,501
	Canopy Soffit (Framing & Exterior Gyp Bd)	1,535 Sf	\$34.19	\$34.19	\$52,481
	Canopy Soffit Hexagon Feature	5 Ea	\$500.00	\$500.00	\$2,500
	Canopy Soffit Edge Framing/Panels	157 Lf	\$168.22	\$168.22	\$26,410
	Wood Blocking Allowance - school	144,355 Sf	\$0.16	\$0.16	\$23,097
F	Wood Blocking Allowance - fieldhouse	32,159 Sf	\$0.16	\$0.16	\$5,145
	Caulking & Sealants - school	144,355 Sf	\$0.08	\$0.08	\$11,548
F	Caulking & Sealants - fieldhouse	32,159 Sf	\$0.08	\$0.08	\$2,573
					\$3,468,851

Exterior Windows & Doors

	Aluminum Window, Low E standard performing glass, triple glazed, integral blinds as indicated, fixed	7,214 Sf	\$95.00	\$95.00	\$685,330
	Add for operable sash	169 Ea	\$500.00	\$500.00	\$84,500
	Add for Ceramic Coated Spandrel	894 Sf	\$10.00	\$10.00	\$8,940
	Add for Insulation @ Spandrel Glass	894 Sf	\$5.30	\$5.30	\$4,738
F	Aluminum Gym Window, Low E standard performing glass, triple glazed, integral blinds as indicated, fixed - fieldhouse	882 Sf	\$95.00	\$95.00	\$83,790
F	Aluminum Fieldhouse Window, Low E standard performing glass, triple glazed, integral blinds as indicated, fixed - fieldhouse	133 Sf	\$95.00	\$95.00	\$12,666
F	Add for operable sash - fieldhouse	6 Ea	\$500.00	\$500.00	\$3,000
	Aluminum Hexagon Window (SF7) - 4' wide	23 Ea	\$1,000.00	\$1,000.00	\$23,000
	Aluminum Storefront, Low E	681 Sf	\$55.00	\$55.00	\$37,455
	Alter Assembly and Add for Integral Blinds	513 Sf	\$60.00	\$60.00	\$30,780
	Aluminum Curtainwall, Low E	3,590 Sf	\$80.00	\$80.00	\$287,200
	Alter Assembly and Add for Integral Blinds	1,761 Sf	\$60.00	\$60.00	\$105,660
	Add for Ceramic Coated Spandrel	1,828 Sf	\$10.00	\$10.00	\$18,280
	Add for Insulation @ Spandrel Glass	1,828 Sf	\$5.30	\$5.30	\$9,688
	Add for Aluminum Lattice - allowance	1,755 Sf	\$60.00	\$60.00	\$105,300
	Alum Entry Door (Leaf)	26 Ea	\$3,000.00	\$3,000.00	\$78,000



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

Slider/Operable Glass Wall Assembly (music)	1 Ea	\$15,750.00	\$15,750.00	\$15,750
ADA Entry Door Opener (per set)	5 Ea	\$5,000.00	\$5,000.00	\$25,000
FRP Door and Alum Frame (3070)	2 Ea	\$3,500.00	\$3,500.00	\$7,000
FRP Doors and Alum Frame (6070)	1 Ea	\$6,000.00	\$6,000.00	\$6,000
F FRP Door and Alum Frame (6070) - fieldhouse	4 Ea	\$6,000.00	\$6,000.00	\$24,000
F Glazing @ Doors (per lite)	6 Ea	\$100.00	\$100.00	\$600
Coiling Door	64 Sf	\$70.00	\$70.00	\$4,480
Caulking & Sealants - school	144,355 Sf	\$0.05	\$0.05	\$7,218
F Caulking & Sealants - fieldhouse	32,159 Sf	\$0.05	\$0.05	\$1,608
				\$1,669,984

Roof

Standing Seam Metal Roof on 5" Rigid Polyiso Insulation w/ Vapor Barrier (<i>incl gutter, downspout, rake edge, vented ridge & snow retention</i>)	25,960 Sf	\$40.00	\$40.00	\$1,038,401
60 mil fleece back TPO Roof (adhered membrane) on Cover Board over 2 layers mech fastened 3" Polyiso (<i>incl tapered insul; vapor barrier; assoc. flashings, gutters, downspouts, etc</i>) 20 yr warranty	69,995 Sf	\$16.30	\$16.30	\$1,140,919
60 mil fleece back TPO Roof (adhered membrane) on Cover Board over 2 layers mech fastened 3" Polyiso (<i>incl tapered insul; vapor barrier; assoc. flashings, gutters, downspouts, etc</i>) 20 yr warranty - Canopy	1,535 Sf	\$16.30	\$16.30	\$25,021
Downspout Boots - PVC	28 Ea	\$200.00	\$200.00	\$5,600
F Downspout Boots - PVC - fieldhouse	13 Ea	\$200.00	\$200.00	\$2,600
Roof Access Hatch	3 Ea	\$2,500.00	\$2,500.00	\$7,500
F Roof Access Hatch - fieldhouse	1 Ea	\$2,500.00	\$2,500.00	\$2,500
Wood Blocking	97,490 Sf	\$0.25	\$0.25	\$24,373
Sealants	97,490 Sf	\$0.05	\$0.05	\$4,875
				\$2,251,787

Interior Partitions

4" C.M.U. Interior Partitions (plumbing chases)	308 Sf	\$14.00	\$14.00	\$4,312
6" C.M.U. Interior Partitions	2,212 Sf	\$14.00	\$14.00	\$30,968
8" C.M.U. Interior Partitions	24,727 Sf	\$14.00	\$14.00	\$346,178
add premium to account for fire wall/barrier	3,388 Sf	\$0.85	\$0.85	\$2,880
F 8" C.M.U. Interior Partitions - fieldhouse	2,602 Sf	\$14.00	\$14.00	\$36,423
F add premium to account for fire wall/barrier - fieldhouse	169 Sf	\$0.85	\$0.85	\$144
F 12" C.M.U. Interior Partitions - fieldhouse	3,276 Sf	\$16.50	\$16.50	\$54,054
F add premium to account for fire wall/barrier - fieldhouse	3,276 Sf	\$1.35	\$1.35	\$4,423
7/8" m.s. w/ batt insul & 1 layer 5/8" gyp bd - self supported furring (B2)	588 Sf	\$4.16	\$4.16	\$2,446
3 5/8" m.s. w/ batt insul & 1 layer 5/8" gyp bd - self supported furring (B4)	28461 Sf	\$6.43	\$6.43	\$183,004
3 5/8" m.s. w/ batt insul & 1 layer 5/8" gyp bd both sides - rated metal stud (C5)	1736 Sf	\$10.54	\$10.54	\$18,297
6" m.s. w/ batt insul & 1 layer 5/8" gyp bd both sides - rated metal stud (C7)	168 Sf	\$10.75	\$10.75	\$1,806
3 5/8" m.s. w/ batt insul & 1 layer 5/8" gyp bd both sides - nonrated metal stud (D5)	99771 Sf	\$9.21	\$9.21	\$918,886
6" m.s. w/ batt insul & 1 layer 5/8" gyp bd both sides - nonrated metal stud (D7)	3973 Sf	\$9.42	\$9.42	\$37,421



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: DD
Date: Date: 5/19/2019 (updated 6/3/19)

Low wall: 6" m.s. w/ 1 layer 5/8" gyp bd both sides (L7)	81 Sf	\$16.75	\$16.75	\$1,348
Add 1 layer 5/8" gyp bd to one side masonry partition (N8)	3052 Sf	\$2.37	\$2.37	\$7,233
Add one layer 1 5/8" furring & 5/8" gyp bd to one side masonry partition (P10)	322 Sf	\$4.03	\$4.03	\$1,298
Add one layer 1 5/8" furring & 5/8" gyp bd to one side masonry partition (P10-1hr)	1960 Sf	\$5.08	\$5.08	\$9,957
Gyp Bd barrier w/ furring attached to underside of CFS	24630 Sf	\$7.62	\$7.62	\$187,681
Drywall Ceiling (framing & gyp bd)	1205 Sf	\$9.62	\$9.62	\$11,590
1 hr rated Drywall Ceiling (framing & gyp bd)	114 Sf	\$10.21	\$10.21	\$1,164
Drywall soffits - vertical of the soffit (framing & gyp bd)	1384 Lf	\$55.65	\$55.65	\$77,020
Drywall soffits - horizontal of the soffit (framing & gyp bd)	6739 Sf	\$9.62	\$9.62	\$64,832
Gyp Board Closure at Op Partition/Coiling Door	510 Lf	\$130.00	\$130.00	\$66,300
Firestopping - school	144,355 Sf	\$0.10	\$0.10	\$14,436
F Firestopping - fieldhouse	32,159 Sf	\$0.10	\$0.10	\$3,216
Wood Blocking - school	144,355 Sf	\$0.18	\$0.20	\$28,871
F Wood Blocking - fieldhouse	32,159 Sf	\$0.18	\$0.20	\$6,432
Caulking & Sealants - school	144,355 Sf	\$0.12	\$0.12	\$17,323
F Caulking & Sealants - fieldhouse	32,159 Sf	\$0.12	\$0.12	\$3,859
				\$2,143,800

Interior Windows & Doors

Alum Entry Door (Leaf)	21 Ea	\$3,000.00	\$3,000.00	\$63,000
Aluminum Storefront	699 Sf	\$55.00	\$55.00	\$38,445
Aluminum Curtainwall	260 Sf	\$80.00	\$80.00	\$20,800
Wood Door W/HM Frame (3070)	225 Ea	\$1,400.00	\$1,400.00	\$315,000
F Wood Door W/HM Frame (3070) - fieldhouse	2 Ea	\$1,400.00	\$1,400.00	\$2,800
F additional @ fire wall - fieldhouse	1 Ea	\$1,000.00	\$1,000.00	\$1,000
Wood Door W/HM Frame (6070)	31 Ea	\$2,265.00	\$2,265.00	\$70,215
additional @ fire wall	7 Ea	\$2,000.00	\$2,000.00	\$14,000
F Wood Door W/HM Frame (6070) - fieldhouse	2 Ea	\$2,265.00	\$2,265.00	\$4,530
F additional @ fire wall - fieldhouse	2 Ea	\$2,000.00	\$2,000.00	\$4,000
Wood Door W/HM Frame (7070)	4 Ea	\$2,570.00	\$2,570.00	\$10,280
HM Door and Frames (3070)	10 Ea	\$1,300.00	\$1,300.00	\$13,000
F HM Door and Frames (3070) - fieldhouse	1 Ea	\$1,300.00	\$1,300.00	\$1,300
HM Door and Frames (6070)	4 Ea	\$2,400.00	\$2,400.00	\$9,600
F HM Door and Frames (6070) - fieldhouse	1 Ea	\$2,400.00	\$2,400.00	\$2,400
HM Frames (7870)	4 Ea	\$1,400.00	\$1,400.00	\$5,600
Glazing @ Doors (per narrow lite)	88 Ea	\$95.50	\$95.50	\$8,404
Glazing @ Doors (per half lite)	4 Ea	\$145.50	\$145.50	\$582
Glazing @ Doors (per decorative-hexagon lite)	127 Ea	\$300.00	\$300.00	\$38,100
Add for fire rated glazing	14 Sf	\$150.00	\$150.00	\$2,100
F Glazing @ Doors (per narrow lite) - fieldhouse	6 Ea	\$95.50	\$95.50	\$573
F Add for fire rated glazing - fieldhouse	5 Sf	\$150.00	\$150.00	\$750
Add For FR Door Labels	7 Ea	\$150.00	\$150.00	\$1,050
F Add For FR Door Labels - fieldhouse	5 Ea	\$150.00	\$150.00	\$750
Access Doors/Panels	20 Ea	\$250.00	\$250.00	\$5,000
Interior HM Frame (HM1) - hexagon 3'	40 Ea	\$900.00	\$900.00	\$36,000
Interior HM Frame (HM2) - hexagon 2'-6"	5 Ea	\$750.00	\$750.00	\$3,750
Interior HM Frame (HM3) - 2'-10" x 4'-0"	3 Ea	\$720.00	\$720.00	\$2,160
Interior all glass wall system (G)	701 Sf	\$50.00	\$50.00	\$35,050
Interior Glass Smoke Baffle (1'-6"h)	98 Lf	\$75.00	\$75.00	\$7,350
Operable Folding Wall Partition	3,376 Sf	\$48.00	\$48.00	\$162,048
premium for markerboard material	752 Sf	\$20.00	\$20.00	\$15,040
Slider/Operable premium for Glass Wall	1 Ea	\$10,000.00	\$10,000.00	\$10,000
Coiling Counter Door	72 Sf	\$70.00	\$70.00	\$5,040



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: DD
Date: Date: 5/19/2019 (updated
6/3/19)

F	Overhead Door - fieldhouse	128 Sf	\$40.00	\$40.00	\$5,120
F	Add Electric Opener	2 Ea	\$950.00	\$950.00	\$1,900
	Aluminum Overhead Door with Glass Infill (5' wide x 8' high)	4 Ea	\$4,650.00	\$4,650.00	\$18,600
	Caulking & Sealants - school	144,355 Sf	\$0.05	\$0.05	\$7,218
F	Caulking & Sealants - fieldhouse	32,159 Sf	\$0.05	\$0.05	\$1,608
					\$944,163

Interior Finishes

	Floor Finishes - Carpet Tile	9,423 Sf	\$4.50	\$4.50	\$42,404
F	Floor Finishes - Carpet Tile - fieldhouse	937 Sf	\$4.50	\$4.50	\$4,217
	Floor Finishes - Walk-off carpet tile	2,046 Sf	\$8.00	\$8.00	\$16,365
	Floor Finishes - Sheet Vinyl	7,949 Sf	\$6.30	\$6.30	\$50,081
	Floor Finishes - LVT	111,654 Sf	\$6.65	\$6.65	\$742,498
	Floor Finishes - Wood	1,810 Sf	\$12.00	\$12.00	\$21,725
	Floor Finishes - Resinous Flooring	4,598 Sf	\$11.80	\$11.80	\$54,253
F	Floor Finishes - Fluid Applied Sports Floor	30,810 Sf	\$8.40	\$8.40	\$258,806
	Floor Finishes - Sealed Concrete	6,519 Sf	\$0.75	\$0.75	\$4,889
F	Floor Finishes - Sealed Concrete - fieldhouse	1,876 Sf	\$0.75	\$0.75	\$1,407
	Floor Finishes - Rubber Stair Treads & Risers	600 Lfr	\$30.00	\$30.00	\$18,000
	Floor Finishes - Rubber Landings	215 Sf	\$12.50	\$12.50	\$2,688
	Floor Finishes - Wood Stair Treads	679 Sf	\$15.00	\$15.00	\$10,185
	Floor Finishes - Wood Stair Risers	125 Lfr	\$15.00	\$15.00	\$1,875
	Floor Finishes - Wood Stair Risers (double height)	347 Lfr	\$30.00	\$30.00	\$10,410
	Floor Finishes - Wood Landings	152 Sf	\$15.00	\$15.00	\$2,280
	Rubber Base - 4" Cove	18,595 Lf	\$2.00	\$2.00	\$37,189
F	Rubber Base - 4" Cove - fieldhouse	1,136 Lf	\$2.00	\$2.00	\$2,272
	Sheet Vinyl Flash Cove Base	2,513 Lf	\$10.00	\$10.00	\$25,129
	Resinous Base	682 Lf	\$12.80	\$12.80	\$8,735
	Ceiling Finishes - ACT-1 (based on Fine Fissured School Zone)	110,471 Sf	\$4.26	\$4.26	\$470,606
F	Ceiling Finishes - ACT-1 (based on Fine Fissured School Zone) - fieldhouse	937 Sf	\$4.26	\$4.26	\$3,992
	Ceiling Finishes - ACT-2 (Ultima)	4,469 Sf	\$6.24	\$6.24	\$27,886
	Ceiling Finishes - ACT-3 (Optima)	2,500 Sf	\$6.28	\$6.28	\$15,702
	Ceiling Finishes - ACT-4 (2x4) scrubbable	4,793 Sf	\$6.84	\$6.84	\$32,783
	Ceiling Finishes - ACT-5 (2x4) scrubbable	3,989 Sf	\$6.84	\$6.84	\$27,284
	Ceiling Finishes - Additional Special Finish/Cloud Allowance	1 Ls	\$100,000.00	\$100,000.00	\$100,000
	Ceiling Finishes - WD/Linear Mtl Ceiling - Armstrong Metalworks	5,350 Sf	\$39.02	\$39.02	\$208,757
	Ceiling Finishes - Exposed Painted	12,867 Sf	\$1.30	\$1.30	\$16,727
F	Ceiling Finishes - Exposed Painted - fieldhouse	31,080 Sf	\$1.30	\$1.30	\$40,404
	Ceiling Finishes - Paint Gypsum/Plaster/EIFS	1,319 Sf	\$0.95	\$0.95	\$1,253
	Ceiling Finishes - Paint Soffit	10,891 Sf	\$0.95	\$0.95	\$10,347
	Wall Finishes - Additional Interior Design Features Allowance	1 Ls	\$100,000.00	\$100,000.00	\$100,000
	Wall Finishes - Paint	169,103 Sf	\$0.95	\$0.95	\$160,647
F	Wall Finishes - Paint - fieldhouse	26,085 Sf	\$0.95	\$0.95	\$24,781
	Wall Finishes - Epoxy Paint	20,005 Sf	\$2.25	\$2.25	\$45,012
	Wall Finishes - High Performance Paint	21,519 Sf	\$3.00	\$3.00	\$64,557
	Wall Finishes - Accent Painting	1 Ls	\$10,000.00	\$10,000.00	\$10,000
	Wall Finishes - Ceramic Tile	3,745 Sf	\$11.00	\$11.00	\$41,195
	Cement Backing Board at Wall Tile	3,745 Sf	\$2.00	\$2.00	\$7,490
	Wall Finishes - FRP	328 Sf	\$6.00	\$6.00	\$1,968
	Wall Finishes - Senory Room Wall Pads	1,760 Sf	\$20.00	\$20.00	\$35,200
	Acoustical Wall Panels - student dining	398 Sf	\$30.00	\$30.00	\$11,948
	Acoustical Wall Panels - small music rooms	158 Ls	\$30.00	\$30.00	\$4,725



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: Estimate Type: DD
Date: Date: 5/19/2019 (updated
6/3/19)

	Acoustical Allowance - large music room	1 Ls	\$15,000.00	\$15,000.00	\$15,000
	Acoustical Allowance - other school areas	1 Ls	\$15,000.00	\$15,000.00	\$15,000
F	Acoustical Allowance - fieldhouse	1 Ls	\$80,000.00	\$80,000.00	\$80,000
	Paint Steel Columns	49 Ea	\$250.00	\$250.00	\$12,250
	Paint HM Frames	326 Ea	\$99.65	\$99.65	\$32,486
F	Paint HM Frames - fieldhouse	6 Ea	\$99.65	\$99.65	\$598
	Paint HM Door	18 Ea	\$100.65	\$100.65	\$1,812
F	Paint HM Door - fieldhouse	3 Ea	\$100.65	\$100.65	\$302
	Paint Metal Pan Stairs	6 Ea	\$903.00	\$903.00	\$5,418
					\$2,941,537

Specialties/Fittings

	Display Case	10 Lf	\$600.00	\$600.00	\$6,000
	Enclosed Bulletin Board Displays w/ LED Strip Lighting	80 Lf	\$250.00	\$250.00	\$20,000
	Tackless Display Rail	429 Lf	\$25.00	\$25.00	\$10,725
	Tack Board (4' or 5' high)	280 Lf	\$70.00	\$70.00	\$19,600
	Marker Board (4' or 5' high)	1,304 Lf	\$80.00	\$80.00	\$104,320
	Magnetic Glassboard (4' or 5' high)	142 Lf	\$115.00	\$115.00	\$16,330
	Pencil Sharpener & Mounting Plate	78 Ea	\$75.00	\$75.00	\$5,850
	Toilet Partition Solid Plastic - Handicap	10 Ea	\$990.00	\$990.00	\$9,900
	Toilet Partition Solid Plastic - Standard	15 Ea	\$615.00	\$615.00	\$9,225
	Hand Dryer	66 Ea	\$600.00	\$600.00	\$39,600
F	Hand Dryer - fieldhouse	2 Ea	\$600.00	\$600.00	\$1,200
	Grab Bar Set (Toilet - 3 bar)	56 Set	\$210.00	\$210.00	\$11,760
F	Grab Bar Set (Toilet - 3 bar) - fieldhouse	2 Set	\$210.00	\$210.00	\$420
	Grab Bar (HC-Shower)	4 Ea	\$140.00	\$140.00	\$560
F	Grab Bar (HC-Shower) - fieldhouse	2 Ea	\$140.00	\$140.00	\$280
	Paper Towel Disp. (Lbr Only)	168 Ea	\$30.00	\$30.00	\$5,040
F	Paper Towel Disp. (Lbr Only) - fieldhouse	2 Ea	\$30.00	\$30.00	\$60
	Toilet Paper Dispenser (Lbr Only)	71 Ea	\$20.00	\$20.00	\$1,420
F	Toilet Paper Dispenser (Lbr Only) - fieldhouse	2 Ea	\$20.00	\$20.00	\$40
	Soap Dispenser (Lbr Only)	176 Ea	\$20.00	\$20.00	\$3,520
F	Soap Dispenser (Lbr Only) - fieldhouse	2 Ea	\$20.00	\$20.00	\$40
	Sanitary Napkin Disposal	28 Ea	\$85.00	\$85.00	\$2,380
F	Sanitary Napkin Disposal - fieldhouse	2 Ea	\$85.00	\$85.00	\$170
	Sanitary Napkin Vendor	7 Ea	\$500.00	\$500.00	\$3,500
F	Sanitary Napkin Vendor - fieldhouse	2 Ea	\$500.00	\$500.00	\$1,000
	Shower Enclosure	4 Ea	\$980.00	\$980.00	\$3,920
F	Shower Enclosure - fieldhouse	2 Ea	\$980.00	\$980.00	\$1,960
	Shower Seat	4 Ea	\$170.00	\$170.00	\$680
F	Shower Seat - fieldhouse	2 Ea	\$170.00	\$170.00	\$340
	Shower Curtain / Rod	4 Ea	\$129.00	\$129.00	\$516
F	Shower Curtain / Rod - fieldhouse	2 Ea	\$129.00	\$129.00	\$258
	Towel/Robe/Coat Hook	82 Ea	\$15.00	\$15.00	\$1,230
F	Towel/Robe/Coat Hook - fieldhouse	4 Ea	\$15.00	\$15.00	\$60
	Child Changing Table	2 Ea	\$405.00	\$405.00	\$810
	Mirror 18" x 36"	46 Ea	\$225.00	\$225.00	\$10,350
F	Mirror 18" x 36" - fieldhouse	2 Ea	\$225.00	\$225.00	\$450
	Mirror 24" x 60"	18 Ea	\$300.00	\$300.00	\$5,400
F	Mirror 24" x 60" - fieldhouse	2 Ea	\$300.00	\$300.00	\$600
	Mirror 60" x 36"	10 Ea	\$450.00	\$450.00	\$4,500
	Mirror	210 Sf	\$30.00	\$30.00	\$6,300
F	Fieldhouse Locker Type - Single Tier Athletic 12"x18"x42"	12 Ea	\$275.00	\$275.00	\$3,300
F	Fieldhouse Locker Type - Double Tier Athletic 12"x18"x66"	20 Ea	\$300.00	\$300.00	\$6,000
	Custodial Lockers 15" w (15x15)	6 Ea	\$200.00	\$200.00	\$1,200



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: Estimate Type: DD
Date: Date: 5/19/2019 (updated
6/3/19)

F	Storage Lockers 15" w (15x15) - fieldhouse	6 Ea	\$200.00	\$200.00	\$1,200
	Kitchen Lockers 12" w - 2 tier	6 Ea	\$200.00	\$200.00	\$1,200
	Janitor Closet Acc (Mop Holder)	5 Ea	\$121.80	\$121.80	\$609
F	Janitor Closet Acc (Mop Holder) - fieldhouse	1 Ea	\$121.80	\$121.80	\$122
	Fire Extinguishers and Cabinets	40 Ea	\$300.00	\$300.00	\$12,000
F	Fire Extinguishers and Cabinets - fieldhouse	8 Ea	\$300.00	\$300.00	\$2,400
	AED Defibrillator Cabinet Only	2 Ea	\$500.00	\$500.00	\$1,000
	Cubical Curtain & Track	62 Lf	\$75.00	\$75.00	\$4,650
	Corner Guards - Vinyl Acrylic, Adhesive Mnt, 1"x1" (CG-1; 8'h)	2,064 Lf	\$10.65	\$10.65	\$21,982
	Corner Guards - Vinyl Cover, Alum Retainer, Surface Mount, 2"x2" (CG-2; 8'h)	808 Lf	\$23.75	\$23.75	\$19,190
	Time Capsule	1 Ea	\$1,250.00	\$1,250.00	\$1,250
	Knox Box	2 Ea	\$1,500.00	\$1,500.00	\$3,000
	Exterior Bldg Numbering, Placards, Sticker Signage	1 Ls	\$7,500.00	\$7,500.00	\$7,500
	Dedication Plaque	1 Ea	\$2,500.00	\$2,500.00	\$2,500
	Interior Bldg Signage	144,355 Sf	\$0.45	\$0.45	\$64,960
F	Interior Bldg Signage - fieldhouse	32,159 Sf	\$0.25	\$0.25	\$8,040
					\$472,416

Food Service

	Dining Food Service Equipment - full prep	1 Ls	\$780,000.00	\$780,000.00	\$780,000
					\$780,000

Casework

Educational & Art Casework

	Base Cabinet Plastic Laminate (no tops)	1459 Lf	\$140.00	\$140.00	\$204,260
	Countertops Plastic Laminate	1459 Lf	\$40.00	\$40.00	\$58,360
	Laminated Counter w/ brace supports	165 Lf	\$80.00	\$80.00	\$13,200
F	Laminated Counter w/ brace supports - fieldhouse	15 Lf	\$80.00	\$80.00	\$1,200
	Laminated Floating Shelf	128 Lf	\$100.00	\$100.00	\$12,800
	Wall Cabinet Plastic Laminate	1772 Lf	\$105.00	\$105.00	\$186,060
F	Wall Cabinet Plastic Laminate - fieldhouse	12 Lf	\$105.00	\$105.00	\$1,260
	Cubbies w/ Wall Cabinet - Plastic Laminate	657 Lf	\$300.00	\$300.00	\$197,100
	Tall Cabinets Plastic Laminate	380 Lf	\$275.00	\$275.00	\$104,500
	Mobile Casework Units (LF)	8 Lf	\$250.00	\$250.00	\$2,000
	Art Base Cabinet	46 Lf	\$200.00	\$200.00	\$9,200
	Art Countertops (Phenolic Resin)	46 Lf	\$100.00	\$100.00	\$4,600
	Art Wall Cabinet	46 Lf	\$125.00	\$125.00	\$5,750
	Art Tall Cabinets or Open Shelving	67 Lf	\$325.00	\$325.00	\$21,775
	Bench	40 Lf	\$200.00	\$200.00	\$8,000
	Reception Desk	15 Lf	\$525.00	\$525.00	\$7,875
	Circulation Desk	21 Lf	\$525.00	\$525.00	\$11,025
	Student Lockers - Double Tier Plastic Laminate Clad (60"h)	510 Lf	\$260.00	\$260.00	\$132,600
	Laminate Locker Surround w/ mitered waterfall edge (top)	12 Lf	\$60.00	\$60.00	\$720
	Laminate Locker Surround (top)	20 Lf	\$35.00	\$35.00	\$700
	Laminate Locker Surround (end panel)	3 Ea	\$150.00	\$150.00	\$450
	Wood cap and P-lam shelf @ Media Area	23 Lf	\$145.00	\$145.00	\$3,335
	Wood cap @ Stairs	137 Lf	\$65.00	\$65.00	\$8,905
	Activity Wall	13 Ea	\$1,600.00	\$1,600.00	\$20,800
	Built-In Hexagonal Nook	8 Ea	\$3,000.00	\$3,000.00	\$24,000
	Metal Storage Shelving	263 Lf	\$125.00	\$125.00	\$32,875
F	Metal Storage Shelving - fieldhouse	36 Lf	\$125.00	\$125.00	\$4,500
<u>Music Casework</u>					
	Tall Music Cabinets Plastic Laminate	112 Lf	\$400.00	\$400.00	\$44,800



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

Library Casework

84"h Bookcase	21 Lf	\$300.00	\$300.00	\$6,300
84"h Bookcase w/ built in Bench Seat	28 Lf	\$500.00	\$500.00	\$14,000
44"h Bookcase	101 Lf	\$250.00	\$250.00	\$25,250

\$1,168,200

Athletics

F Gym Divider Curtain	6,048 Sf	\$6.50	\$6.50	\$39,312
Electronic Control System & Keypad	1 Ls	\$5,000.00	\$5,000.00	\$5,000
F Motorized Basketball Backstop Assembly (Ceiling Susp Forward Fold Front Braced)	12 Ea	\$6,120.00	\$6,120.00	\$73,440
F Volleyball System w/ Posts, Net, Judges Stand, Cart	4 Ea	\$3,530.00	\$3,530.00	\$14,120
F Badminton Net and Standards	4 Ea	\$1,900.00	\$1,900.00	\$7,600
F Wall Padding (2'x6')	80 Ea	\$230.00	\$230.00	\$18,400
F Tip and Roll Bleachers (w/FFE)	0 Unit	\$0.00	\$0.00	\$0
F Electro Mech LX2655 Multi Sport Scoreboard 10'x6'	8 Ea	\$9,965.00	\$9,965.00	\$79,720
F Floor Covering System (per court)	4 Ea	\$13,250.00	\$13,250.00	\$53,000
F Chin Up Bar - Adjustable	1 Ea	\$355.00	\$355.00	\$355
F Pegged Board Vertical Climber	1 Ea	\$425.00	\$425.00	\$425
F Tumbling Mat (4'x8'x2")	10 Ea	\$250.00	\$250.00	\$2,500
F Tumbling Mat Cart	1 Ea	\$1,500.00	\$1,500.00	\$1,500
F Ball & Equipment Racks - Allowance	1 Ls	\$5,000.00	\$5,000.00	\$5,000

\$300,372

Theatrical

Stage Curtain (no rigging)	1 Ls	\$28,000.00	\$28,000.00	\$28,000
Electrical Projection Screen	1 Ea	\$7,500.00	\$7,500.00	\$7,500

\$35,500

Appliances & Equipment

Miscellaneous Appliances & Equipment (w/FFE)	0 Ea	\$0.00	\$0.00	\$0
Sensory Swing	4 Ea	\$3,875.00	\$3,875.00	\$15,500
Kiln	3 Ea	\$4,450.00	\$4,450.00	\$13,350

\$28,850

Conveying

Electric Traction Passenger Elev. (2 stop)	2 Ea	\$107,500.00	\$107,500.00	\$215,000
--	------	--------------	--------------	-----------

\$215,000

Plumbing

Plumbing Systems (School)	1 Ls	\$2,865,000.00	\$2,865,000.00	\$2,805,000
F Plumbing Systems (Fieldhouse)	1 Ls	\$35,000.00	\$35,000.00	\$35,000
Site Gas	1,230 Lf	\$50.00	\$50.00	\$61,500

\$2,901,500

Fire Protection

Total Fire Protection System (School)	144,355 Sf	\$2.75	\$2.75	\$396,976
F Total Fire Protection System (Fieldhouse)	32,159 Sf	\$2.75	\$2.75	\$88,437
Add for Fire Pump (none anticipated)	0 Ls	\$45,000.00	\$45,000.00	\$0



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

\$485,414

HVAC

HVAC Systems (School)	1 Ls	\$4,164,500.00	\$4,164,500.00	\$4,164,500
F HVAC Systems (Fieldhouse)	1 Ls	\$393,500.00	\$393,500.00	\$393,500

\$4,558,000

Electrical

Electrical Systems (School)	1 Ls	\$4,042,217.00	\$4,042,217.00	\$4,042,217
F Electrical Systems (Fieldhouse)	1 Ls	\$620,000.00	\$620,000.00	\$620,000
* Primary Transformer Purchase Allowance	1 Ls	\$150,000.00	\$150,000.00	\$150,000

\$4,812,217

Technology

Technology and Cabling (School)	1 Ls	\$1,501,000.00	\$1,501,000.00	\$1,501,000
F Technology and Cabling (Fieldhouse)	1 Ls	\$223,000.00	\$223,000.00	\$223,000

\$1,724,000

Site Demolition

Clearing	22 Acre	\$5,000.00	\$5,000.00	\$110,000
Remove House & Shed	1 Ls	\$10,000.00	\$10,000.00	\$10,000
Remove Above Ground Tank	1 Ls	\$5,000.00	\$5,000.00	\$5,000
Remove Gate	1 Ls	\$500.00	\$500.00	\$500
Remove Fence	420 Lf	\$10.00	\$10.00	\$4,200
Remove Overhead Electric	1,500 Lf	\$10.50	\$10.50	\$15,750
Misc Sawcutting	1 Ls	\$1,500.00	\$1,500.00	\$1,500
Misc Undesignated Site Demolition	1 Ls	\$2,500.00	\$2,500.00	\$2,500

\$149,450

Site Preparation

Survey	1 Ls	\$12,000.00	\$12,000.00	\$12,000
Gravel Construction Entrance	2 Ls	\$3,500.00	\$3,500.00	\$7,000
Laydown Area	1 Ls	\$85,000.00	\$85,000.00	\$85,000
Sweep Streets	5 Ls	\$1,000.00	\$1,000.00	\$5,000
Erosion Control Filter Sock	7,800 Lf	\$8.00	\$8.00	\$62,400
Erosion Control Blankets	9,725 Sy	\$2.25	\$2.25	\$21,881
Erosion Control, Concrete Washout	1 Ea	\$900.00	\$900.00	\$900
Erosion Control, Skimmer	2 Ls	\$5,500.00	\$5,500.00	\$11,000
Erosion Control, Inlet Protection	31 Ea	\$125.00	\$125.00	\$3,875
Erosion Control - Upkeep	104 Wks	\$150.00	\$150.00	\$15,600
Temp Seeding	127,500 Sf	\$0.16	\$0.16	\$20,400
Strip and Stockpile Topsoil (use some as fill in yards)	33,995 Cy	\$3.00	\$3.00	\$101,985
Cuts	16,068 Cy	\$5.50	\$5.50	\$88,374
Fills in Hard Surface Areas	23,000 Cy	\$4.50	\$4.50	\$103,500
Fills in Yard Areas	23,262 Cy	\$3.50	\$3.50	\$81,417
Misc Site Grading	1 Ls	\$12,000.00	\$12,000.00	\$12,000
Install #304 under Building Pad (6")	4,375 Tons	\$22.00	\$22.00	\$96,250
Grading under the Building Pad	15,000 Sy	\$1.35	\$1.35	\$20,250
Grading under HD Pavement	25,679 Sy	\$1.35	\$1.35	\$34,667
Grading under SD Pavement	2,211 Sy	\$1.35	\$1.35	\$2,985
Grading under Concrete Pavement	2,099 Sy	\$1.35	\$1.35	\$2,834
Grading under Mechanical Area	138 Sy	\$1.35	\$1.35	\$186



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: Estimate Type: DD
Date: Date: 5/19/2019 (updated 6/3/19)

Grading under Soft Play Area	2,146 Sy	\$1.35	\$1.35	\$2,897
Prep under Sidewalks	3,425 Sy	\$2.50	\$2.50	\$8,563
Prep for Curb	9,745 Lf	\$3.25	\$3.25	\$31,671
Working surface for winter earthwork schedule - Cement Stabilize Building Pad 12" @ 6 %	15,000 Sy	\$12.00	\$12.00	\$180,000
Workable site for winter earthwork schedule - Lime Stabilize Paved Areas (single lift/1 time)	30,127 Sy	\$9.00	\$9.00	\$271,140
Undercut, Load & Export soils at pad and lot areas over 4' fill (PSI #304 option - no 90 day wait time)	4,296 Cy	\$24.00	\$24.00	\$103,104
Import/Install #304 (PSI #304 option - no 90 day wait time)	7,518 Tons	\$20.00	\$20.00	\$150,360
Additional Drying Techniques to achieve proper moisture for using onsite material as fill - Allowance	1 Ls	\$135,000.00	\$135,000.00	\$135,000
				\$1,672,238

Site Pavings

HD Asphalt Drive /Base	219,825 Sf	\$4.74	\$4.74	\$1,041,971
HD Asphalt Drive /Base (auxilliary drive to Blossom)	11,285 Sf	\$4.74	\$4.74	\$53,491
SD Asphalt Drive /Base	19,900 Sf	\$4.22	\$4.22	\$83,978
Parking/Drive Striping	1 Ls	\$4,800.00	\$4,800.00	\$4,800
Playground Striping	1 Ls	\$10,000.00	\$10,000.00	\$10,000
8" Reinforced HD Concrete Pavement on 8" Base	18,890 Sf	\$11.33	\$11.33	\$214,024
4" Reinforced Walk on 4" Base	30,825 Sf	\$9.79	\$9.79	\$301,777
adder for integral curb & gutter	1,530 Lf	\$5.67	\$5.67	\$8,675
Concrete Ramp - ADA access	12 Ea	\$1,300.00	\$1,300.00	\$15,600
Stone Berm	2,000 Lf	\$5.15	\$5.15	\$10,300
Stone Berm (auxilliary drive to Blossom)	540 Lf	\$5.15	\$5.15	\$2,781
Rolled Curb	340 Lf	\$21.65	\$21.65	\$7,361
Type 6 Curbs	7,290 Lf	\$19.78	\$19.78	\$144,196
Concrete Curb - PK playground	200 Lf	\$19.78	\$19.78	\$3,956
Concrete Curb - Elementary playground	385 Lf	\$19.78	\$19.78	\$7,615
Oakes Road traffic improvements /widening Allowance	1 Ls	\$500,000.00	\$500,000.00	\$500,000

\$2,410,524

Site Improvements

Seat Wall	190 Lf	\$120.00	\$120.00	\$22,800
Concrete Steps	40 Lfr	\$75.00	\$75.00	\$3,000
Amphitheater Steps (double wide)	140 Lfr	\$100.00	\$100.00	\$14,000
Railing	55 Lf	\$100.00	\$100.00	\$5,500
8'h Masonry Enclosure (trash/mech)	118 Lf	\$437.20	\$437.20	\$51,590
8'h Masonry Divider - cmu only (trash/mech)	27 Lf	\$260.80	\$260.80	\$7,042
add for dbl gate	2 Ea	\$2,000.00	\$2,000.00	\$4,000
add for oversized dbl gate	2 Ea	\$4,000.00	\$4,000.00	\$8,000
Chain Link Fence - vinyl coated (4'h) elementary play /pond	1,230 Lf	\$30.00	\$30.00	\$36,900
Chain Link Single Gate (4' high; 4' opening)	5 Ea	\$750.00	\$750.00	\$3,750
Decorative Fence (4'H) - PK playground	200 Lf	\$65.00	\$65.00	\$13,000
Man Gate (4'H)	2 Ea	\$800.00	\$800.00	\$1,600
Decorative Fence (4'H) - outdoor dining	90 Lf	\$65.00	\$65.00	\$5,850
Man Gate (4'H)	1 Ea	\$800.00	\$800.00	\$800
Flag Pole (40')	1 Ea	\$4,000.00	\$4,000.00	\$4,000
Basketball Backboard/Post	4 Ea	\$2,500.00	\$2,500.00	\$10,000
Bike Rack	8 Ea	\$350.00	\$350.00	\$2,800



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: 176,514
Estimate Type: DD
Date: 5/19/2019 (updated 6/3/19)

Benches (w/FFE)	0 Ea	\$1,300.00	\$1,300.00	\$0
Trash Receptacles (w/FFE)	0 Ea	\$675.00	\$675.00	\$0
Table (w/FFE)	0 Ea	\$2,700.00	\$2,700.00	\$0
Mulch Play Area - 12"	16,000 Sf	\$3.50	\$3.50	\$56,000
Stone Base @ Play Area	16,000 Sf	\$2.00	\$2.00	\$32,000
Poured in Place Safety Playground Surface	3,310 Sf	\$12.50	\$12.50	\$41,375
Stone Base @ Poured in Place Safety Surface	3,310 Sf	\$2.00	\$2.00	\$6,620
New PK & Relocated Elementary Playground Equip Allowance	1 Ls	\$100,000.00	\$100,000.00	\$100,000
Building Letters (12" Alum)	44 Ea	\$200.00	\$200.00	\$8,800
F Building Letters (12" Alum)	19 Ea	\$200.00	\$200.00	\$3,800
Monumental Building Sign - Allowance	1 Ea	\$40,000.00	\$40,000.00	\$40,000
Exterior Post & Panel Signs	3 Ea	\$1,500.00	\$1,500.00	\$4,500
Traffic & HC Parking Signs w/base	38 Ea	\$210.00	\$210.00	\$7,980
Stone Mechanical Yard	1240 Sf	\$2.50	\$2.50	\$3,100

\$498,806

Site Landscaping

Landscaping - Shade Trees	60 Ea	\$450.00	\$450.00	\$27,000
Landscaping - Ornamental Trees/Flowering Trees	10 Ea	\$440.00	\$440.00	\$4,400
Landscaping - Evergreen Trees	42 Ea	\$330.00	\$330.00	\$13,860
Landscaping - Lg Shrubs	25 Ea	\$145.00	\$145.00	\$3,625
Landscaping - Plantings	9,695 Sf	\$2.50	\$2.50	\$24,238
2-3" Bark Mulch Bed @ plantings	2,502 Sy	\$8.75	\$8.75	\$21,890
Seeding (lawn - various mixes)	487,485 Sf	\$0.18	\$0.18	\$87,747
Spread Topsoil	9,240 Cy	\$7.50	\$7.50	\$69,300

\$252,059

Site Water

4" Domestic Line	1,292 Lf	\$45.00	\$45.00	\$58,140
8" Water Line	2,577 Lf	\$68.00	\$68.00	\$175,236
6" Water Line	175 Lf	\$68.00	\$68.00	\$11,900
Domestic riser in building	1 Ea	\$3,100.00	\$3,100.00	\$3,100
Fire riser in building	1 Ea	\$3,500.00	\$3,500.00	\$3,500
8" tees, bends, plugs	19 Ea	\$280.00	\$280.00	\$5,320
4" tees, bends, plugs	4 Ea	\$280.00	\$280.00	\$1,120
Sawcut road and repair for tap	1 Ls	\$1,500.00	\$1,500.00	\$1,500
Connect to Ex w/12x8 tapping sleeve and valve	1 Ea	\$4,700.00	\$4,700.00	\$4,700
Fire Hydrant assemblies, incl tee, valve & pipe	6 Ea	\$5,500.00	\$5,500.00	\$33,000
Fire Dept Connection	1 Ea	\$3,500.00	\$3,500.00	\$3,500
Traffic Control	1 Ls	\$2,000.00	\$2,000.00	\$2,000
Testing/bag and flush	1 Ls	\$5,000.00	\$5,000.00	\$5,000
Combined meter pit	1 Ea	\$48,000.00	\$48,000.00	\$48,000

\$356,016

Site Gas

Gas Line (w/ plumbing)	0 Lf	\$50.00	\$50.00	\$0
------------------------	------	---------	---------	-----

\$0

Site Sanitary

6" Sewer in pavement	520 Lf	\$66.00	\$66.00	\$34,320
8" Sewer in pavement	308 Lf	\$72.00	\$72.00	\$22,176
8" Sewer in yard	316 Lf	\$55.00	\$55.00	\$17,380



Brecksville-Broadview Heights CSD

Brecksville, OH
Elementary School & Field House

New G.S.F.: New G.S.F.: 176,514
Estimate Type: Estimate Type: DD
Date: Date: 5/19/2019 (updated
6/3/19)

Sanitary Sewer Cleanouts	1 Ea	\$500.00	\$500.00	\$500
4' manhole	3 Ea	\$4,200.00	\$4,200.00	\$12,600
Grease Trap	1 Ls	\$5,800.00	\$5,800.00	\$5,800
Doghouse manhole on EX line 11 feet deep	1 Ls	\$7,500.00	\$7,500.00	\$7,500
Sanitary testing	1,144 Lf	\$2.00	\$2.00	\$2,288
				\$102,564

Site Storm

Concrete Barrier Curb underdrain	7,290 Lf	\$12.50	\$12.50	\$91,125
4" Underdrains	5,040 Lf	\$14.00	\$14.00	\$70,560
4" finger drains	1,100 Lf	\$14.00	\$14.00	\$15,400
10" DS Pipe	204 Lf	\$31.00	\$31.00	\$6,324
8" DS Pipe	540 Lf	\$27.00	\$27.00	\$14,580
6" DS Leaders	60 Lf	\$23.00	\$23.00	\$1,380
Tees, Bends, etc. for DS	45 Ea	\$45.00	\$65.00	\$2,925
12" Storm	1,273 Lf	\$32.00	\$32.00	\$40,736
15" Storm	785 Lf	\$42.00	\$42.00	\$32,970
18" Storm	375 Lf	\$49.00	\$49.00	\$18,375
24" Storm	706 Lf	\$52.00	\$52.00	\$36,712
30" Storm	430 Lf	\$66.00	\$66.00	\$28,380
Catch Basin curb inlet	14 Ea	\$3,700.00	\$3,700.00	\$51,800
Catch Basin 2-2B	6 Ea	\$1,350.00	\$1,350.00	\$8,100
Rip Rap at outlets	95 Tons	\$50.00	\$50.00	\$4,750
Storm manholes	2 Ea	\$2,700.00	\$2,700.00	\$5,400
60" Storm manholes	1 Ea	\$5,200.00	\$5,200.00	\$5,200
Storm Outlet Control Structure	2 Ea	\$7,000.00	\$7,000.00	\$14,000
30" Headwalls	3 Ea	\$850.00	\$850.00	\$2,550
24" Headwalls	1 Ea	\$675.00	\$675.00	\$675
15" Headwalls	2 Ea	\$550.00	\$550.00	\$1,100
12" Headwalls	3 Ea	\$550.00	\$550.00	\$1,650
Storm Clean, Flush, Test, & CCTV	4,373 Lf	\$4.00	\$4.00	\$17,492
				\$472,184

Value Engineering Ideas

Brecksville-Broadview Heights CSD
Elementary School & Field House
DD

Fieldhouse Total - Hard Cost Estimate	\$	7,647,251
Fieldhouse Total - Hard Cost Budget	\$	7,236,769
Fieldhouse Budget Difference - (over) / under	\$	(410,482)
Fieldhouse VE ACCEPTED	\$	304,415
Alternates Added Back Into Base Bid	\$	-
Additional VE Still Required (Fieldhouse)	\$	(106,067) Over Budget

Overall Budget Difference: -\$6,812,231.14
(pre-VE)

		VE Savings	(A)cccept (R)eject	Planned (A)lternate	Comments
<i>FH</i>	Foundations				
1					
<i>FH</i>	Substructure				
1					
<i>FH</i>	Superstructure				
1					
<i>FH</i>	Fabrications				
1					
<i>FH</i>	Exterior Closure				
1					
<i>FH</i>	Exterior Windows & Doors				
1	Revise exterior gym windows to translucent panels	\$ 22,050	a	\$ 22,050	
2	Further reduction of gym windows from 9' high to 4'-6" hight(square foot reduction of half)	\$ 11,025			
3	Manual Window Shades at east elevation Windows/Operable Storefront Units in lieu of Integral Blinds	\$ 1,667	a	\$ 1,667	
<i>FH</i>	Roof				
1					
<i>FH</i>	Interior Partitions				
1					
<i>FH</i>	Interior Windows & Doors				
1					
<i>FH</i>	Interior Finishes				
1	Reduce Acoustical Allowance - Fieldhouse by 1/2	\$ 40,000	a	\$ 40,000	a \$ 40,000
<i>FH</i>	Specialties/Fittings				
1					
<i>FH</i>	Food Service				
1					

<i>FH</i> Casework						
1	Move Metal Storage Shelving to FFE	\$ 4,500				
<i>FH</i> Athletics						
1	Reduce the number of basketball backstops by 4 each (8 remain)	\$ 29,014	a	\$ 29,014	a	\$ 58,028
2	Eliminate the floor covering system	\$ 53,000	a	\$ 53,000		
3	Reduce the 8 ~ scoreboards from a 10'x6' size to an 8'x4' size	\$ 38,560	a	\$ 38,560		
<i>FH</i> Theatrical Equipment						
1						
<i>FH</i> Equipment						
1						
<i>FH</i> Conveying						
1						
<i>FH</i> Plumbing						
1						
<i>FH</i> Fire Protection						
1						
<i>FH</i> HVAC						
1						
<i>FH</i> Electrical						
1	Eliminate Lightning Protection	\$ 24,625				
2	First Energy to Supply Transformer in lieu of City/School	\$ 75,000	a	\$ 75,000		
<i>FH</i> Technology & Cabling						
1						
<i>FH</i> Site Demolition (50% of Value)						
1						
<i>FH</i> Site Preparation (50% of Value)						
1						
<i>FH</i> Site Pavings (50% of Value)						
1	Eliminate pavement and gravel berms at Auxilliary Drive to Blossom	\$ 28,136	a	\$ 28,136		
2	Revise the HD pavement at staff/visitor/FH parking area and internal lanes to SD (isolated drives to remain HD)	\$ 16,988	a	\$ 16,988		
3	Revise the HD pavement at access drive to SD	\$ 3,463				
4	Revise bus dropoff & pickup/ auxilliary lot to bus drive only (eliminates 120 space auxiliary lot and bus zone becomes curb parking both sides)	\$ 34,539				
5	Push the access drive south of building to edge of walk just south of fieldhouse	\$ 9,212				
<i>FH</i> Site Improvements (NONE IN FIELDHOUSE SCOPE)						
1						

alternate creates cross courts at 2 instead of using port

FH portion of scope (50%); no upfront cost & buyback later with other funding

scope outside of project

<i>FH</i>	Site Landscaping (50% of Value)					
1						
<i>FH</i>	Site Utilities (50% of Value)					
1						
<i>FH</i>	Technology					
1						
<i>FH</i>	Loose Furnishings/FFE					
1						
<i>FH</i>	Other Options					
1	Redesign FH 1	\$	270,257			
1a	Additional savings to redesign FH 2	\$	81,296			

TOTAL POTENTIAL VE SAVINGS (FIELDHOUSE) \$ 743,333

TOTAL ACCEPTED VE SAVINGS (FIELDHOUSE) \$ 304,415 **POTENTIAL ALTERNATES \$ 98,028**

Elementary School Total - Hard Cost Estimate	\$	39,754,287
Elementary School Total - Hard Cost Budget	\$	33,352,538
Elementary School Budget Difference - (over) / under	\$	(6,401,749)
Elementary School VE ACCEPTED	\$	2,870,161
Alternates Added Back Into Base Bid	\$	-
Additional VE Still Required (Elementary School)	\$	(3,531,588) <i>Over Budget</i>

		VE Savings	(A)cccept (R)reject	Planned (A)lternate	Comments
<i>Elem</i>	Foundations				
1					
<i>Elem</i>	Substructure				
1	Omit Learning Stair (1st floor area becomes floor space; 2nd floor railing extends across opening - floor space remains as is)	\$	55,637		
2	Music/Stage area to remain at grade (not elevated above student dining) - also reduces height at dining portion by 30"	\$	89,738	a	\$ 89,738
<i>Elem</i>	Superstructure				
1					
<i>Elem</i>	Fabrications				
1	Steel Picket handrail at Learning Stair/ 1st & 2nd Floor Media Area Spaces in lieu of Aluminum with Glass	\$	20,151	a	\$ 20,151
<i>Elem</i>	Exterior Closure				

1a	Revise Stone Veneer area to Fiber Cement Panel	\$	6,215						
1a	Further Reduce Stone Veneer area to Brick Veneer	\$	4,031						
2	Eliminate hexagon pattern at split face CMU - std split face instead	\$	29,813	p	\$	14,906			
3	Brick veneer to split face (std - no pattern) at court yard elevations	\$	29,882	a	\$	29,882			
4a	Fiber cement panels throughout to be replaced with non-insulated concealed fastener metal panels.	\$	60,163						
4b	Further reduce fiber cement (now metal panel) area @ west elevation. Replace panels at K-1 wing with brick.	\$	17,710	a	\$	17,710			savings increased assuming 4a was not accepted
4c	Similar to 4b at east elevation of 2/3 wing.	\$	7,852						
4d	Similar to 4b at north elevation of 4/5 wing.	\$	7,852						

Elem **Exterior Windows & Doors**

1	Non-insulated metal panel on stud wall in lieu of curtainwall/spandrel/lattice combination in all areas indicating aluminum lattice	\$	178,010	a	\$	178,010			
2	Manual Window Shades at Windows/Operable Storefront Units (Classrooms) in lieu of Integral Blinds	\$	90,175	a	\$	90,175			
3	Manual Window Shades at Storefronts/Curtainwalls (band, library, dining, etc.) in lieu of Integral Blinds	\$	80,727	a	\$	80,727			
4	Reduce height of CW2 @ library by 6' (or otherwise reduce by 150 sf)	\$	6,929	a	\$	6,929			
5	Reduce width of SF11 @ dining by 8'-3" (82 sf)	\$	2,983	a	\$	2,983			

Elem **Roof**

1	Use TPO in lieu of fleece back TPO at Low Sloped Roof	\$	60,801	a	\$	60,801	a	\$	60,801	
2a	Asphalt shingles in lieu of sloped metal roof	\$	519,200	a	\$	519,200	a	\$	100,000	alternate is for additional 10 warranty (30 tears total)
2b	Further reduction to eliminate the 2 sloped roof sections at the K/1 Wing (TPO instead)	\$	228,266	a	\$	228,266				
2c	Further reduction to eliminate the 4 remaining sloped roof sections (TPO instead)	\$	456,531	p	\$	114,133				
3	Eliminate canopies at main bus entry, entry near FH, and PK entry. Main entrance canopy @ east elevation to remain.	\$	60,249	p	\$	20,000				eliminate pk canopy only
4	Eliminate main entrance canopy.	\$	73,255							

Elem **Interior Partitions**

1	Replace the drywall ceiling portion of collaborative spaces (D100, D120, C100, C120, D200, D220, C200, C220) with ACT-1	\$	12,090	a	\$	12,090			
2	Eliminate soffits at east side of Corridor A1C01 and run ACT-1 straight through instead	\$	5,088						
3	Eliminate soffits at east side of Corridor C2C01 and run ACT-1 straight through instead	\$	5,811						

Elem **Interior Windows & Doors**

1	Eliminate doors between Kindergarten and 1st grade classrooms	\$	24,560	a	\$	24,560			
2	Revise decorative lites (hexagon) in doors to narrow lites throughout	\$	25,972	a	\$	25,972			
3	Eliminate HM1 & HM2 - interior hexagon windows throughout (classrooms, collaborative, etc)	\$	39,750						
4	Eliminate Operable Partitions between K-Classroom & Collaborative (B115 & B113) and between 1st grade Classroom & Collaborative (B215 & B213)	\$	11,053	a	\$	11,053			
5	Eliminate Operable Partitions between Collaborative Spaces D100/D120, D200/D220, C100/C120, C200/C220	\$	28,908						
6	Eliminate Operable Partitions between Classrooms at Grades 2-5 (D104/D105, D124/D125, D204/D205, D224/D225, C104/C105, C124/C125, C204/C205, C224/C225)	\$	44,212	a	\$	44,212			
7	Eliminate Operable Partitions between Project Labs at Grades 2-5 (D101/D102, D121/D122, D201/D202, D221/D222, C101/C102, C121/C122, C201/C202, C221/C222)	\$	95,227	a	\$	95,227			
8	Eliminate the G1 Panel of All Glass Wall System at south end of Maker A111	\$	9,995						
9	Eliminate the G2 Panels of All Glass Wall System at east and west ends of Maker A111	\$	11,045	a	\$	11,045			

<i>Elem</i> Interior Finishes						
1	Revise LVT to 75% carpet tile and 25% LVT in 46 classrooms (not project labs)	\$	55,631			
2	LVT at Stage in lieu of Wood	\$	9,686	a	\$	9,686
3a	ACT-2 in lieu of WD/Linear Mtl Ceiling at Student Dining	\$	175,373	a	\$	175,373
3b	Further reduction to ACT-1	\$	10,593	a	\$	10,593
3c	Further reduction to eliminate soffit at south side of Dining and run ACT-1 straight through	\$	7,125	a	\$	7,125
4	Eliminate Sensory Room Wall Pads	\$	35,200			
5a	Reduce Additional Special Finish/Cloud Allowance by 1/2	\$	50,000	a	\$	50,000
5b	Further reduction to eliminate remainder of allowance	\$	50,000			
6a	Reduce Additional Interior Design Features Allowance by 1/2	\$	50,000	a	\$	50,000
6b	Further reduction to eliminate remainder of allowance	\$	50,000			
7a	Reduce 'Acoustical Allowance - large music room' by 1/2	\$	7,500	a	\$	7,500
7b	Further reduction to eliminate remainder of allowance	\$	7,500			
8a	Reduce 'Acoustical Allowance - other school areas' by 1/2	\$	7,500	a	\$	7,500
8b	Further reduction to eliminate remainder of allowance	\$	7,500			
<i>Elem</i> Specialties/Fittings						
1	Eliminate Display Case at Reception A100	\$	6,000			
2	Eliminate Lighted Bulletin Board Display Cases	\$	20,000	a	\$	20,000
3	Replace Hand Dryers with Paper Towel Dispensers	\$	37,620			
4	Eliminate Corner Guards (CG-1) - primarily at corners within classrooms & other individual rooms	\$	21,982			
5	Eliminate Corner Guards (CG-2) - primarily in common spaces	\$	19,190			
6	Cut back on signage to standard needs/ typical school (eliminate signage on A930.2, etc.)	\$	21,653	a	\$	21,653
<i>Elem</i> Food Service						
1						
<i>Elem</i> Casework						
1	Move Metal Storage Shelving to FFE	\$	32,875	a	\$	32,875
2	Minimize Casework (eliminate 20% base cabinets, counter, & wall cabinets overall - avg of 4 lf of each per classroom, collaborative area, and project lab)	\$	89,736			
3	Eliminate Built-In Hexagon Nooks @ Collaborative Areas	\$	24,000			
4	Eliminate Activity Walls @ Collaborative Areas	\$	20,800			
5	Eliminate Built-In Bench at Reception A100	\$	8,000	a	\$	8,000
<i>Elem</i> Athletics						
1						
<i>Elem</i> Theatrical Equipment						
1	Eliminate Stage Equipment/Stage Curtain	\$	28,000			
<i>Elem</i> Equipment						
1	Eliminate Sensory Swings (any available for reuse?)	\$	15,500	?		checking for reuse potential?
<i>Elem</i> Conveying						
1	Revise traction elevators (2) to hydraulic	\$	25,000			
2	Further reduction to completely eliminate one elevators (one hydraulic elevator remains)	\$	99,950			
<i>Elem</i> Plumbing						
1	Allow a standard TMV (mixing valve) in lieu of a digital TMV	\$	8,000	a	\$	8,000

- 2 Allow copper Propress in lieu of copper solder
- 3 Cost effective design elements moving into GMP phase (fixture selection, competition in specifications, etc.)
- 4 Reduce sinks in project labs from 3 to 1 (8 rooms)

\$	50,000	a	\$	50,000		
\$	60,000	a	\$	60,000		
\$	80,000	a	\$	80,000		

Elem **Fire Protection**

1						
---	--	--	--	--	--	--

Elem **HVAC**

1						
---	--	--	--	--	--	--

Elem **Electrical**

- 1 Eliminate Lightning Protection
- 2 First Energy to Supply Transformer in lieu of City/School
- 3 Eliminate 'stage' lighting at platform
- 4 Cost effective design elements moving into GMP phase (aluminum feeders, fixture selection, competition in specifications, etc.)

\$	75,751	a	\$	75,751		
\$	75,000	a	\$	75,000		
\$	40,000					
\$	40,000	a	\$	40,000		

school portion of scope (50%); no upfront cost & buyback later with other funding

Elem **Technology & Cabling**

1						
---	--	--	--	--	--	--

Elem **Site Demolition (50% of Value)**

1						
---	--	--	--	--	--	--

Elem **Site Preparation (50% of Value)**

1						
---	--	--	--	--	--	--

Elem **Site Pavings (50% of Value)**

- 1 Eliminate Auxilliary Drive to Blossom
- 2 Revise the HD pavement at staff/visitor/FH parking area and internal lanes to SD (isolated drives to remain HD)
- 3 Revise the HD pavement at access drive to SD
- 4 Revise bus dropoff & pickup/ auxilliary lot to bus drive only (eliminates 120 space auxiliary lot and bus zone becomes curb parking both sides)
- 5 Push the access drive south of building to edge of walk just south of fieldhouse

\$	28,136	a	\$	28,136		
\$	16,988	a	\$	16,988		
\$	3,463					
\$	34,539					
\$	9,212					

Elem **Site Improvements (100% of Value)**

- 1 Chain link fence instead of masonry enclosure at dumpster
- 2 Vinyl coated chain link fence instead of aluminum ornamental fence @ PK playground and Outdoor Dining
- 3 Eliminate Outdoor Dining Area (including vestibule)
- 4 Reduce the Area of Elementary Mulch Play from 16000 sf to 8000 sf
- 5 Revise the poured in place playground surface at the PK play to mulch
- 6 Eliminate the Outdoor Classroom at the Music Area (including exterior operable wall & amphitheater steps)

\$	54,381	a	\$	54,381		
\$	10,300	a	\$	10,300		
\$	60,448					
\$	47,671	a	\$	47,671		
\$	29,790					
\$	51,721	p	\$	25,860.56		

Elem **Site Landscaping (50% of Value)**

1						
---	--	--	--	--	--	--

Elem **Site Utilities (50% of Value)**

1					
	Elem	Technology			
1					
	Elem	Loose Furnishings/FFE			
1		Fund Playground Equipment (new & relocated) out of loose furnishings budget	\$ 100,000	a	\$ 100,000
2		Additional Transfer of FFE dollars to building budget (leaves \$25,000 for FH; \$100,000 for playground allowance; \$10/sf of school)	\$ 100,000	a	\$ 100,000
	Elem	Other Options			
1		Eliminate the PK wing	\$ 886,130		
2		Eliminate the PK wing - additional savings based on 6/3/19 VE status	\$ 34,790		

TOTAL POTENTIAL VE SAVINGS (ELEMENTARY SCHOOL) \$ 5,290,113

TOTAL ACCEPTED VE SAVINGS (ELEMENTARY SCHOOL)	\$ 2,870,161	POTENTIAL ALTERNATES	\$ 213,047
---	--------------	----------------------	------------