

<u>Location</u>	<u>Description</u>	<u>Takeoff Quantity</u>	<u>Total Cost/Unit</u>	<u>Total Amount</u>
Option 1-Replace (5) Tennis Courts				
	<u>Quality Control</u>			
	Testing			By Owner
	<u>Traffic/Security Controls</u>			
	Construction Fencing - 4' High Orange Fence	1,020.00 lf	4 /lf	4,080
	Access Roads/Laydown - 8"	620 sy	46.35 /sy	28,737
	<u>Miscellaneous</u>			
	Building Permits	1 ls	2500 /ls	2,500
	<u>Final Cleaning</u>			
	Dumpster Charges - 30 Cy	3 ea	525 /ea	1,575
	Final Clean-Up	3 md	650 /md	1,950
	<u>Demolition</u>			
	Remove Existing Fencing & Misc Site Items	1 ls	4,000.00 /ls	4,000
	Remove existing asphalt paving	3,723.00 sy	9 /sy	33,507
	<u>Topsoil Stripping</u>			
	Strip & Stockpile Topsoil - D3 200'	410 cy	4.26 /cy	1,747
	<u>Fine Grading</u>			
	Compact Subgrade-Tennis Courts	3,723.00 sy	1.8 /sy	6,701
	Fine Grade Subgrade	6,200.00 sy	1.35 /sy	8,370
	<u>Rolled Erosion Control Mats</u>			
	Furnish Silt Fence	1,000.00 lf	2 /lf	2,000
	Inlet Protection	3 ea	150 /ea	450
	Install Silt Fence	1,000.00 lf	1.12 /lf	1,120
	<u>Flexible Paving</u>			
	Asphalt Paving (SY) & Sub-Base for Tennis Courts	3,725.00 sy	34 /sy	126,650
	<u>Athletic Surfacing</u>			
	Tennis Court Nets & Posts	5 ea	1,600.00 /ea	8,000
	Tennis Court Surfacing	33,500.00 sf	1.45 /sf	48,575
	<u>Chain Link Fence</u>			
	New 12' High Chain-Link Fences & Gates	975 lf	75 /lf	73,125
	<u>Grading & Seeding</u>			
	Spread Topsoil-Assume 6"	410 cy	49.05 /cy	20,111
	<u>Seeding</u>			
	Seed Disturbed Areas	22,100.00 sf	0.17 /sf	3,757
	<u>Subcontract Utilities Systems</u>			
	Storm Utility Allowance	1 allo	75,000.00 /allo	75,000
	Option 1-Total Estimated Cost			451954.50
	Cost per Court			90390.90
	Cost per Court (Less Storm Utility Allowance)			75390.90

<u>Option #1-Replace (5) Existing Tennis Courts</u>			
Subtotal - Cost of Work from Above		\$451,955	
Add Phasing/Working Conditions		N/A	
Add Escalation-2% Assumed		\$ 9,039	
Add Preconstruction Services - TBD		\$ 4,500	
Add Construction Contingency-5% TBD		\$ 23,275	
Add Estimating Contingency-5%		\$ 24,438	
Add CMR General Conditions-Lump Sum		\$ 50,353	
Add CMR Fee-4% TBD		\$ 22,542	
Total Estimated Project Cost w/Estimate Contingency (not incl soft costs)		\$586,102	\$ 82.90

<u>Location</u>	<u>Description</u>	<u>Takeoff Quantity</u>	<u>Total Cost/Unit</u>	<u>Total Amount</u>
Option 3-Provide (2) New Tennis Courts				
	<u>Field Engineering</u>			
	Layout	2 day	684.94 /day	1,370
	<u>Quality Control</u>			
	Testing Allowance			By Owner
	<u>Traffic/Security Controls</u>			
	Construction Fencing - 4' High Orange Fence	500 lf	4 /lf	2,000
	Access Roads/Laydown - 8"	1 ls	7500 /ls	7,500
	<u>Miscellaneous</u>			
	Building Permits	1 ls	2500 /ls	2,500
	<u>Demolition</u>			
	Remove Existing Fencing & Misc Site Items	1 ls	950 /ls	950
	<u>Topsoil Stripping</u>			
	Strip & Stockpile Topsoil	280 cy	5.09 /cy	1,425
	<u>Fine Grading</u>			
	Compact Subgrade-Tennis Courts	1,425.00 sy	1.8 /sy	2,565
	Fine Grade Subgrade	3,200.00 sy	1.35 /sy	4,320
	<u>Hauling</u>			
	Strip & Haul Material for New Asphalt Tennis Courts	390 cy	29 /cy	11,310
	<u>Rolled Erosion Control Mats</u>			
	Furnish Silt Fence	825 lf	2 /lf	1,650
	Inlet Protection	2 ea	150 /ea	300
	Install Silt Fence	825 lf	1.12 /lf	924
	<u>Flexible Paving</u>			
	Asphalt Paving (SY) & Sub-Base for Tennis Courts	1,425.00 sy	34 /sy	48,450
	<u>Sidewalks</u>			
	New 6' wide walking surface to Tennis Courts	2,500.00 sf	7.25 /sf	18,125
	<u>Athletic Surfacing</u>			
	Tennis Court Nets and Posts	2 ea	1,600.00 /ea	3,200
	Bleacher Allowance	1 allo	3,800.00 /allo	3,800
	Tennis Court Surfacing	12,820.00 sf	1.45 /sf	18,589
	<u>Chain Link Fence</u>			
	New 12' High Chain-Link Fences & Gates	450 lf	75 /lf	33,750
	<u>Ground Covers</u>			
	Spread Topsoil-Assume 6"	290 cy	48 /cy	13,920
	Seed Areas Disturbed	15,585.00 sf	0.17 /sf	2,649
Option 3-Total Estimated Cost				179297.53
Cost per Court				89648.765

<u>Option #3-Install (2) New Courts</u>	
Subtotal - Cost of Work from Above	\$ 179,298
Add Phasing/Working Conditions	N/A
Add Escalation-2% Assumed	\$ 3,586
Add Preconstruction Services - TBD	\$ 4,500
Add Construction Contingency-5% TBD	\$ 9,369
Add Estimating Contingency-5%	\$ 9,838
Add CMR General Conditions-Lump Sum	\$ 33,078
Add CMR Fee-4% TBD	\$ 9,587
Total Estimated Project Cost w/Estimate Contingency (not incl soft costs)	\$ 249,255
<u>Option #3-Install (2) New Courts w/ Alt #1</u>	
Add Alt #1-Replace (3) ex. city courts	\$ 298,917
Total Estimated Project Cost w/ Alt #1	\$ 548,172

\$ 35.26