

<u>Location</u>	<u>Description</u>	<u>Takeoff Quantity</u>	<u>Total Cost/Unit</u>	<u>Total Amount</u>
Option 3-Resurface (5) Tennis Courts				
	<u>Quality Control</u>			
	Testing			By Owner
	<u>Traffic/Security Controls</u>			
	Access Roads/Laydown - 8"	20 sy	46.35 /sy	927
	<u>Miscellaneous</u>			
	Building Permits	1 ls	2500 /ls	2,500
	<u>Final Cleaning</u>			
	Dumpster Charges - 30 Cy	1 ea	525 /ea	525
	<u>Demolition</u>			
	Remove Existing Fencing & Misc Site Items	1 ls	2,000.00 /ls	2,000
	<u>Erosion Control</u>			
	Inlet Protection	3 ea	150 /ea	450
	<u>Flexible Paving & Athletic Surface</u>			
	Asphalt Paving - 1/2" leveling course, fabric, 1.5" overlay, (4) coats acrylic play surface	1.00 ls	142500 /ls	142,500
	<u>Athletic Surfacing</u>			
	Tennis Court Nets & Posts	5 ea	1,600.00 /ea	8,000
	<u>Chain Link Fence</u>			
	New 12' High Chain-Link Fences & Gates	1 ls	6000 /ls	6,000
	<u>Grading & Seeding</u>			
	Spread Topsoil-Assume 6"	20 cy	49.05 /cy	981
Option 1-Total Estimated Cost				\$ 163,883
Cost per Court				\$ 32,777

<u>Option #3-Resurface (5) Existing Tennis Courts</u>			
Subtotal - Cost of Work from Above	\$	163,883	
Add Phasing/Working Conditions		N/A	
Add Escalation-2% Assumed	\$	3,278	
Add Preconstruction Services - TBD	\$	4,500	
Add Construction Contingency-5% TBD	\$	8,583	
Add Estimating Contingency-5%	\$	9,012	
Add CMR General Conditions-Lump Sum	\$	50,353	
Add CMR Fee-4% TBD	\$	9,584	
Total Estimated Project Cost w/Estimate Contingency (not incl soft costs)	\$	249,193	\$ 35.25
<u>Alternate #1 - 4" Overlay</u>			
Alternate #1-Add 2" base course	\$	75,332	
Total Estimated Project Cost w/ Alt #1	\$	324,525	