

Cost Issue Review



Project: BBH MS FA Replacement

Project # 118060

To: Ryan Schmit (rschmit@thendesign.com)

From: Shook Construction

Chris Coad (coadc@bbhcsd.org)

Phone:

Page: 9, including cover sheet

Re: Issue #01, Bulletin #2 Rev

Date: 9/17/2019

☐ Urgent ☒ For Review ☐ Please Comment ☒ Please Reply ☒ Please Approve

Description:

Please see the attached cost issue submitted by Shook Construction per Bulletin #02 revision #1 and RFI #05 response which included the revisions / added devices for fire department review and added devices to C.I.T.E. area.

Cost Breakdown

Einheit Electric Construction Co.	\$ 41,848.95
CMr Contingency (0%)	\$ -
CMr Bond (0.53%)	\$ 221.80
CMr Liability Insurance (0.00%)	\$ -
CMr CAT Tax (0.00%)	\$ -
CMr Staffing & GC's	\$ -
CMr Fee (2.15%)	\$ 967.63
Total	\$ 43,038.38

ThenDesign should sign below acknowledging acceptance of this Cost Issue and e-mail this coversheet to School District for their approval.

Accepted by:

ThenDesign

Date

Accepted by:

Owner Representative

Date

Accepted by:

Owner – School District

Date



Date: September 12, 2019
Project: BBHMS Fire Alarm Replacement

To: Eric Gradert
Project Manager
Shook Construction
6860 W. Snowville Road, Suite 100
Brecksville, Ohio 44141

From: Einheit Electric Construction Co.

Via: ☐ Hand Deliver/Courier
☒ Email
☐ Mail/UPS/Fedex

Description:

Attached is RFCE-4 reflecting pricing for Bulletin #2 Revision #1 and associated RFI-E005 documents.



240 Tuxedo Ave. Cleveland Ohio 44131
 (216) 661-6000 □ Fax (216) 661-4924
 "ESTABLISHED MAY 1910"

Additional Work Authorization Forms

Project Name:

BBHMS FA Replacement

RFCE-4: Work as shown in Bulletin #2 Rev #1 & RFI-E005 response & sketch

Labor:		Hours	Rate	Average	Extension
Grouped Labor 2nd Shift		808.00	83.60		\$67,548.80
		0.00			\$0.00
		0.00			\$0.00
		0.00			\$0.00
					\$0.00
Sub-Total:					\$67,548.80
Misc. Material		Amount	Tax Rate	Tax Amount	Extension
Take-off Material		\$9,487.43	0.00%	\$0.00	\$9,487.43
Consumables		\$404.00	0.00%	\$0.00	\$404.00
Paladin Quote		\$19,495.00	0.00%	\$0.00	\$19,495.00
		\$0.00	0.00%	\$0.00	\$0.00
Sub-Total:					\$29,386.43
Sub Contractor	Quantity	Amount	Tax Rate	Tax Amount	Extension
Tele/Data		\$0.00	0.00%	\$0.00	\$0.00
Laborer		\$0.00	0.00%	\$0.00	\$0.00
Back hoe		\$0.00	0.00%	\$0.00	\$0.00
Hauling, landfill and Surcharges		\$0.00	0.00%	\$0.00	\$0.00
		\$0.00	0.00%	\$0.00	\$0.00
Sub-Total:					\$0.00
General Conditions:	Quantity	Amount	Tax Rate	Tax Amount	Extension
Shop Truck		\$0.00	0.00%	0.0%	\$0.00
CAD		\$0.00	0.00%	0.0%	\$0.00
Warranty		\$0.00	0.00%	0.0%	\$0.00
		\$0.00	0.00%	0.0%	\$0.00
Sub-Total:					\$0.00
Expenses	Quantity	Amount	Tax Rate	Tax Amount	Extension
Lift Rental	1	\$2,115.00	0.00%	\$0.00	\$2,115.00
		\$0.00	0.00%	\$0.00	\$0.00
		\$0.00	0.00%	\$0.00	\$0.00
		\$0.00	0.00%	\$0.00	\$0.00
Sub-Total:					\$2,115.00
Recapitulation:					
Labor:		\$67,548.80			
Misc. Material:		\$29,386.43			
Sub Contractor:		\$0.00			
General Conditions:		\$0.00			
Expenses:		\$2,115.00			
Cost:		\$99,050.23			
Overhead:	10.00%	\$9,905.02			
Markup:	5.00%	\$4,952.51			
Sub-Total:		\$113,907.76			
Bond:	2.00%	\$2,278.16			
Total Price:		\$116,185.92			

COST BREAKDOWN

Einheit Electric

240 Tuxedo Ave
Cleveland, OH 44128
Telephone: 216-518-5500
Fax: 216-661-4924

Date: 9/12/2019
Project Name: BBHMS FA
Project Number: 1987
RFCE #: 4

Work Description

Bulletin #2 Rev #1 & RFI-E005 Response & Sketch

Itemized Breakdown

Description	Qty	Net Price	C	Total Mat(\$)
! 3/4" CONDUIT - EMT	100	77.78	C	\$ 77.78
! 1" CONDUIT - EMT	57	133.66	C	\$ 76.19
3/4" CONN SS STL - EMT	15	217.80	C	\$ 32.67
3/4" COUPLING SS STL - EMT	6	255.96	C	\$ 15.36
3/4" INSULATING BUSHING - EMT	13	26.10	C	\$ 3.39
1" INSULATING BUSHING - EMT	40	93.63	C	\$ 37.45
3/4x CLOSE NIPPLE - RMC - GALV	1	129.50	C	\$ 1.30
3/4" LOCKNUT - STEEL	1	48.54	C	\$ 0.49
3/4" BUSHING - PLASTIC	1	31.32	C	\$ 0.31
3/4" 1-H STRAP - RMC - STEEL	10	68.98	C	\$ 6.90
3/4" 1-H STRAP - EMT - STEEL	6	47.26	C	\$ 2.84
1/2 OR 3/4" SNAP CLOSE CLIP - BTM MNT ON 1/4" FLNG HNGR	7	149.83	C	\$ 10.49
1" SNAP CLOSE CLIP - BTM MNT ON 1/4" FLNG HNGR	80	179.13	C	\$ 143.30
1/2" FLEX - STEEL	12	104.70	C	\$ 12.56
3/4" FLEX - STEEL	105	142.50	C	\$ 149.63
1/2" CONN FLEX DC SQUEEZE STRAIGHT	4	125.78	C	\$ 5.03
3/4" CONN FLEX DC SQUEEZE STRAIGHT	18	204.19	C	\$ 36.75
1/2" CONN FLEX DC SQUEEZE 90 DEG	4	238.71	C	\$ 9.55
3/4" CONN FLEX DC SQUEEZE 90 DEG	18	421.25	C	\$ 75.83
! #14 THHN BLACK	394	74.58	M	\$ 29.38
! #12 THHN BLACK	130	118.98	M	\$ 15.47
! #12 THHN GREEN	65	118.98	M	\$ 7.73
#18- 1P F/A CABLE 125 DEG PLENUM	4,687	315.35	M	\$ 1,478.05
#16- 1P F/A CABLE 125 DEG PLENUM	380	447.13	M	\$ 169.91
#14- 1P F/A CABLE 125 DEG PLENUM	3,704	618.45	M	\$ 2,290.74
WIRE CONN YEL	66	13.93	C	\$ 9.19
1/8" POLYTWINE	6,056	13.76	M	\$ 83.33
4x 1 1/2" SQ BOX COMB KO	4	644.64	C	\$ 25.79
4x 2 1/8" SQ BOX COMB KO	98	1,026.71	C	\$ 1,006.18
4" SQ BOX EXT RING COMB KO	43	870.73	C	\$ 374.41
4" SQ BLANK COVER	28	239.72	C	\$ 67.12
V700 ONE-PIECE RACEWAY + ACCESSORIES	577	179.00	C	\$ 1,032.83
#8 TO #10x 7/8 PLAS ANCHOR (3/16)	169	7.20	C	\$ 12.17

Itemized Breakdown

Description	Qty	Net Price	C	Total Mat(\$)
1/4-20x 1/2 HEX HEAD BOLT - PLTD STL	24	4.34	C	\$ 1.04
1/4-20x 3/4 P/H SLOT/PHILLIPS MACHINE SCREW	42	3.65	C	\$ 1.53
#10x 3/4 P/H SELF-TAP SCREW	8	9.72	C	\$ 0.78
#10x 1 P/H SELF-TAP SCREW	169	10.28	C	\$ 17.37
MALL BEAM CLAMP TO 15/16" FLNG W/ 1/4-20 THRD HOLE BTM+BACK	427	253.60	C	\$ 1,082.87
HAMMER-ON CLIP TO 1/4" FLANGE W/ 1/4-20 HOLE	66	84.33	C	\$ 55.66
1 1/4" BRIDLE RING - 1/4-20 THRD	427	141.66	C	\$ 604.89
24" SPAN T-BAR HNGR FOR 1 1/2" SQ BOX	43	765.73	C	\$ 329.26
2G BLANK-STRAP MNT PLATE - NYLON IVY	2	102.50	C	\$ 2.05
F/A PULL STATION 1-STAGE - ADDRESSABLE	4	0.01	C	\$ 0.00
F/A DETECTOR - PHOTOELECTRIC SMOKE - ADDRESSABLE	85	0.01	C	\$ 0.01
F/A DETECTOR - FIXED TEMP HEAT - ADDRESSABLE	12	0.01	C	\$ 0.00
F/A DETECTOR BASE LOW PROFILE - ADDRESSABLE	101	0.01	C	\$ 0.01
F/A CARBON MONOXIDE DETECTOR	4	0.01	C	\$ 0.00
F/A DETECTOR - PHOTOELECTRIC DUCT	4	0.01	C	\$ 0.00
F/A DUCT DETECTOR SAMPLING TUBE - 2' TO 4' WIDTH	8	0.01	C	\$ 0.00
F/A SURFACE BOX (RED) PULL STATION - 1 GANG	8	0.01	C	\$ 0.00
F/A SURFACE BOX (RED) - 2 GANG	42	0.01	C	\$ 0.00
F/A STROBE - WALL MNT	4	0.01	C	\$ 0.00
F/A SPEAKER+STROBE - 4" WALL MNT	6	0.01	C	\$ 0.00
CONTROL MODULE MULTIPLEX	17	0.01	E	\$ 0.17
MONITOR MODULE MULTIPLEX	5	0.01	E	\$ 0.05
F/A VERIFICATION - PER INITIATING DEVICE	114	0.01	C	\$ 0.01
F/A VERIFICATION - PER SIGNALLING DEVICE	10	0.01	C	\$ 0.00
F/A VERIFICATION - PER ANCILLARY POINT	17	0.01	E	\$ 0.17
#12 WIRE POWER TERM	3	0.01	C	\$ 0.00
FIRESTOP COMPOUND CAULK TUBE	7	12.50	E	\$ 87.50
DEMO F/A PULL STATION	2	0.01	C	\$ 0.00
DEMO F/A STROBE ONLY	3	0.01	C	\$ 0.00
DEMO F/A HORN / STROBE	8	0.01	C	\$ 0.00
DEMO F/A DUCT SMOKE DETECTOR	1	0.01	C	\$ 0.00
DEMO FA EXTENDER PANEL	1	0.01	C	\$ 0.00
FA EXTENDER PANEL	1	0.01	C	\$ 0.00
TIE MONITOR MODULE INTO HOOD SUPPRESSION SYSTEM	1	0.01	C	\$ 0.00
TIE CONTROL MODULE INTO AHU SHUTDOWN	12	0.01	C	\$ 0.00
WALL PENETRATION	40	0.01	C	\$ 0.00
REMOVE / REPLACE CEILING TILE	623	0.63	C	\$ 3.92
FISH CABLES TO SURF MOUNT BOX	18	0.01	C	\$ 0.00
FIRE CURTAIN TIE-IN	1	0.01	C	\$ 0.00
				9,487.43



Paladin
7680 Hub Parkway
Valley View, OH 44125
216-441-6500 Fax 216-573-2774
Donna Kish

Einheit Electric Construction Co.
Joshua Patterson
240 Tuxedo Avenue
Cleveland, OH 44131

9/9/2019
** Quotation **
Project Number: 49832R1
Brecksville BVH Bulletin #2 FA

Tel: 216-661-6000

Fax: 216-661-4924

Tel: 216-661-6000

Qty	Mfr-Part No.	Description
-----	--------------	-------------

The following is our quotation to provide the Fire Alarm System additions per Bulletin #2 for Brecksville Broadview Heights Middle School.

Our quotation includes the following:

- 1.) Provide (5) Addressable Pull Stations with Surface Boxes
- 2.) Provide (88) Addressable Smoke Detectors
- 3.) Provide (13) Addressable Heat Detectors
- 4.) Provide (5) Addressable Duct Detectors
- 5.) Provide (1) Addressable Relay Module for Fire Curtain
- 6.) Provide (1) Addressable Monitor Module for Kitchen Hood
- 7.) Provide (2) Addressable Relay Modules for Stage AHU Shutdown
- 8.) Provide (2) Addressable Relay Modules for Gym AHU Shutdown
- 9.) Provide (1) Wall Mounted Speaker Strobe with Back Box
- 10.) Provide (1) Wall Mounted Strobe with Back Box
- 11.) Provided a subtotal for (4) Conventional CO Detectors with Addressable Monitor Modules
- 12.) Provide (1) IP Dialer
- 13.) Labor to terminate, program, and test
- 14.) CAD drawing revisions
- 15.) Shipping and Handling

Paladin would like to qualify the following:

- 1.) Electrical Contractor shall be responsible for installation of the materials listed below.

Qty	Mfr-Part No.	Description
		2.) This quotation is based on the drawings that were provide to Paladin based on Bulletin #2.
		3.) Paladin is not responsible for the design of this project.
		4.) If any extra devices are required, additional costs will be applied for labor and materials.
		5.) Contractor shall provide a network drop in the area where the IP Dialer will be located for communication.
		6.) This revised proposal is based on job site meeting where the local fire marshall was in attendance and has approved the removal of several smoke detectors.

NOTE: Sales Tax and Prevailing Wage have not been included.

Notifier - Fire Alarm System Additions per Bulletin #2

=====

IP Dialer

1	LTEV Verizon Alarm Communicator, Commercial Dual Path Fire, Red
1	Installation Hardware

Loop Card

1	LOOP EXPANDER MODULE. MOUNTS AS DAUGHTER BOARD TO LCM-320 TO PR
---	---

Pull Stations

5	ADDRESSABLE NBG-12L PULL STATION; WITH FLASHSCAN.
5	SURFACE BACK-BOX FOR ALL NBG-10 OR NBG-12; EXCEPT NBG-12LRA. MET
5	STOPPER II, NO HORN, SURFACE.

Smoke Detectors

19	INTELLIGENT ADDRESSABLE PHOTO DETECTOR; WITH FLASHSCAN; WHITE
19	AVAILABLE ON/ABOUT MARCH 2018/INTELLIGENT FLANGED MOUNTING BASE;

Duct Detectors

5	INNOVAIRFLEX INTELLIGENT DUCT DETECTOR, NON-RELAY, DOES NOT INCL
5	REMOTE TEST CAPABLE INTELLIGENT PHOTO DETECTOR WITH FLASHSCAN; F
5	INNOVAIRFLEX SAMPLING TUBE, STEEL, 5 WITH HOLES
5	ADDRESSABLE RELAY MODULE WITH FLASHSCAN; PROVIDES TWO FORM-C DRY
5	REMOTE TEST STATION; WITH SWITCH, ALARM AND POWER LEDS.
5	RELAY, SPDT, MULTIVOLT, 24VDC, 24/115VAC

Fire Curtain Relay Module

1	ADDRESSABLE RELAY MODULE WITH FLASHSCAN; PROVIDES TWO FORM-C DRY
---	--

Qty	Mfr-Part No.	Description	
		Kitchen Hood Monitor	
1		ADDRESSABLE MINI MODULE WITH FLASHSCAN; SUPERVISES A CLASS B CIR	
		Stage AHU Shutdown Relay	
2		ADDRESSABLE RELAY MODULE WITH FLASHSCAN; PROVIDES TWO FORM-C DRY	
		Gym AHU Shutdown Relay	
2		ADDRESSABLE RELAY MODULE WITH FLASHSCAN; PROVIDES TWO FORM-C DRY	
		Notification Devices	
1		SPEAKER STROBE RED WALL	
1		WALL MOUNT SPEAKER SURFACE MOUNT BACK BOX, RED	
1		STROBE RED WALL	
1		WALL SURFACE MOUNT BACK BOX, RED	
		Labor to terminate, program, and test	
Total for Notifier Fire Alarm System Additions			7,369.59
		Notifier - Addressable Smoke Detectors in Corridors	
		=====	
51		INTELLIGENT ADDRESSABLE PHOTO DETECTOR; WITH FLASHSCAN; WHITE	
51		AVAILABLE ON/ABOUT MARCH 2018/INTELLIGENT FLANGED MOUNTING BASE; Labor to program and test	
Total for Notifier Smoke Detectors in Corridors			5,506.92
		Notifier - Addressable Smoke Detectors in Storage Rooms	
		=====	
18		INTELLIGENT ADDRESSABLE PHOTO DETECTOR; WITH FLASHSCAN; WHITE	
18		AVAILABLE ON/ABOUT MARCH 2018/INTELLIGENT FLANGED MOUNTING BASE; Labor to program and test	
Total for Notifier Smoke Detectors in Storage Rooms			1,924.56

Qty	Mfr-Part No.	Description
-----	--------------	-------------

Notifier - Addressable Heat Detectors

=====

Heat Detectors

13	INTELLIGENT ADDRESSABLE 135 DEGREE THERMAL DETECTOR WITH FLASHSC
13	AVAILABLE ON/ABOUT MARCH 2018/INTELLIGENT FLANGED MOUNTING BASE; Labor to program and test

Total for Notifier Addressable Heat Detectors

1,285.22

Notifier - System CO Detectors and Modules

=====

4	CONVENTIONAL CARBON MONOXIDE DETECTOR, 12/24 VDC, WITH SOUNDER A
4	ADDRESSABLE MINI MODULE WITH FLASHSCAN; SUPERVISES A CLASS B CIR

Total for System CO Detectors and Modules

1,013.71

By signing below, I acknowledge that I have read and give authorization to proceed with this quotation. I also understand that this signature does not take the place of a Purchase Order and in some cases, one will still be required.

This * * Quotation * * is Valid for 90 Days.

_____/_____
Authorized Signature Date

Print Name / Title _____

Project Total:	\$17,100.00
----------------	-------------