

February 18, 2020

Chris Coad
Director of Business Services
Brecksville-Broadview Heights City School District
1 John Carroll Boulevard
Brecksville, Ohio 44141

Re: Concrete Bleacher Slab Bid
Home Bleacher Renovation - Brecksville-Broadview Heights Stadium

Dear Mr. Coad:

Concrete Bleacher Slab Bid
Scope of Work

1. We have extensively reviewed the home bleacher with Mr. Jon Leuthaeuser, a structural engineer and Associate Principal with Barber & Hoffman. Mr. Leuthaeuser could not find any indication that the existing bleachers foundations and bleachers are physically moving toward the track. Mr. Leuthaeuser is concerned with frost heave of the new bleacher pad and is recommending the construction of a wall along the existing bleacher, prior to constructing the new bleacher pad.
2. To simplify the bleacher construction, we will remove all concrete and fencing along base of the bleachers currently heaving. In addition, we will remove all concrete and fencing along the entire face of the existing bleacher, extending toward the proposed ramp to the north. The uneven concrete will be replaced with a bleacher slab and wall along the existing hillside. The stadium fencing will be replaced by the future bleacher fencing. We will remove all loose hillside material collecting at the bottom of the bleacher and maintain all existing catch basins. We will add subdrainage at the bottom of the existing bleachers to help collect any water on this hillside.
3. Our anticipated estimate for this work, to be competitively bid, is: \$125,000.

If you have any questions, or need additional information, please call me.

Sincerely,

BEHNKE ASSOCIATES, INC.



Marie M. Dowling, ASLA
Principal